




Know what's below
811 before you dig

PROPOSED SUBDIVISION "DIAMOND HILL SUBDIVISION" TAX MAP 409, LOT 228 DIAMOND HILL ROAD, CANDIA, NH

GENERAL LEGEND

EXISTING	PROPOSED	DESCRIPTION
---	---	PROPERTY LINES
---	---	SETBACK LINES
---	---	CENTERLINE
---	---	FRESHWATER WETLANDS LINE
---	---	TIDAL WETLANDS LINE
---	---	STREAM CHANNEL
---	---	TREE LINE
---	---	STONEWALL
---	---	BARBED WIRE
---	---	FENCE
---	---	STOCKADE FENCE
---	---	SOIL BOUNDARY
---	---	AQUIFER PROTECTION LINE
---	---	FLOOD PLAIN LINE
---	---	ZONELINE
---	---	EASEMENT
---	---	MAJOR CONTOUR
---	---	MINOR CONTOUR
---	---	EDGE OF PAVEMENT
---	---	VERTICAL GRANITE CURB
---	---	SLOPE GRANITE CURB
---	---	CAPE COD BERM
---	---	POURED CONCRETE CURB
---	---	SILT FENCE
---	---	DRAINAGE LINE
---	---	SEWER LINE
---	---	SEWER FORCE MAIN
---	---	GAS LINE
---	---	WATER LINE
---	---	WATER SERVICE
---	---	OVERHEAD ELECTRIC
---	---	UNDERGROUND ELECTRIC
---	---	GUARDRAIL
---	---	UNDERDRAIN
---	---	FIRE PROTECTION LINE
---	---	THRUST BLOCK
---	---	IRON PIPE/IRON ROD
---	---	DRILL HOLE
---	---	IRON ROD/DRILL HOLE
---	---	STONE/GRANITE BOUND
---	---	SPOT GRADE
---	---	PAVEMENT SPOT GRADE
---	---	CURB SPOT GRADE
---	---	BENCHMARK (TBM)
---	---	DOUBLE POST SIGN
---	---	SINGLE POST SIGN
---	---	WELL
---	---	TEST PIT
---	---	FAILED TEST PIT
---	---	MONITORING WELL
---	---	PERC TEST
---	---	PHOTO LOCATION
---	---	TREES AND BUSHES
---	---	UTILITY POLE
---	---	LIGHT POLES
---	---	DRAIN MANHOLE
---	---	SEWER MANHOLE
---	---	HYDRANT
---	---	WATER GATE
---	---	WATER SHUT OFF
---	---	REDUCER
---	---	SINGLE GRATE CATCH BASIN
---	---	DOUBLE GRATE CATCH BASIN
---	---	TRANSFORMER
---	---	CULVERT W/WINGWALLS
---	---	CULVERT W/FLARED END SECTION
---	---	CULVERT W/STRAIGHT HEADWALL
---	---	STONE CHECK DAM
---	---	DRAINAGE FLOW DIRECTION
---	---	4K SEPTIC AREA
---	---	WETLAND IMPACT
---	---	VEGETATED FILTER STRIP
---	---	RIPRAP
---	---	PAVEMENT HATCH
---	---	OPEN WATER
---	---	FRESHWATER WETLANDS
---	---	TIDAL WETLANDS
---	---	STABILIZED CONSTRUCTION ENTRANCE
---	---	CONCRETE
---	---	GRAVEL
---	---	SNOW STORAGE
---	---	RETAINING WALL
---	---	STEEP SLOPES



VICINITY MAP
SCALE 1" = 1000'

SHEET INDEX

CS	COVER SHEET
A1	OVERVIEW SUBDIVISION PLAN
A2-A5	SUBDIVISION PLANS
C1-C1B	OVERVIEW EXISTING CONDITIONS PLANS
C2-C5	EXISTING CONDITIONS PLANS
C6	OVERVIEW SITE PLAN
C7-C8	SITE PLANS
C9	OVERVIEW GRADING & DRAINAGE PLAN
C10-C11	GRADING & DRAINAGE PLANS
P1-P7	PROFILE SHEETS
D1-D3	DETAIL SHEETS
E1-E2	EROSION CONTROL SHEET

WAIVERS:

1. SUBDIVISION REGULATIONS SECTION 18.14
2. SUBDIVISION REGULATIONS SECTION 10.6.c
3. SUBDIVISION REGULATIONS SECTION 10.6.u
4. SUBDIVISION REGULATIONS SECTION 12.04
5. SUBDIVISION REGULATIONS SECTION 14.09
6. SUBDIVISION REGULATIONS SECTIONS 19.14
7. SUBDIVISION REGULATIONS SECTION 14.15

PERMITS

TYPE OF PERMIT	STATUS
NHDES ALTERATION OF TERRAIN PERMIT: NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES - WATER DIVISION 29 HAZEN DRIVE, P.O. BOX 95 CONCORD, NEW HAMPSHIRE 03302-0095 (603) 271-3503 RESPONSIBLE CONSULTANT: JONES & BEACH ENGINEERS, INC.	SUBMITTED: PERMIT NO. DATED: EXPIRATION:
NHDES SUBDIVISION PERMIT: NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES - SUBSURFACE SYSTEMS BUREAU 29 HAZEN DRIVE, P.O. BOX 95 CONCORD, NEW HAMPSHIRE 03302-0095 (603) 271-3503 RESPONSIBLE CONSULTANT: JONES & BEACH ENGINEERS, INC.	SUBMITTED: PERMIT NO. DATED: EXPIRATION:
NHDES WETLAND PERMIT: NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES - WETLANDS BUREAU 29 HAZEN DRIVE, P.O. BOX 95 CONCORD, NEW HAMPSHIRE 03302 (603) 271-2147 RESPONSIBLE CONSULTANT: JONES & BEACH ENGINEERS, INC.	SUBMITTED: PERMIT NO. DATED: EXPIRATION:
USEPA NPDES PHASE II CONSTRUCTION GENERAL PERMIT, NOTICE OF INTENT (NOI), AND NOTICE OF TERMINATION (NOT) TO BE FILED IN ACCORDANCE WITH FEDERAL AND LOCAL REGULATIONS PRIOR TO AND FOLLOWING CONSTRUCTION: EPA STORMWATER NOTICE PROCESSING CENTER MAIL CODE 4203M, US EPA 1200 PENNSYLVANIA AVENUE, NW WASHINGTON, DC 20460 RESPONSIBLE CONSULTANT: JONES & BEACH ENGINEERS, INC.	SUBMITTED: PERMIT NO. DATED: EXPIRATION:

CIVIL ENGINEER
JONES & BEACH ENGINEERS, INC.
85 PORTSMOUTH AVENUE
PO BOX 219
STRATHAM, NH 03885
(603) 772-4746
CONTACT: BARRY GIER
E-MAIL: BGIER@JONESANDBEACH.COM

ELECTRIC
EVERSOURCE
740 N COMMERCIAL ST
PO BOX 330
MANCHESTER, NH 03105-0330
(800) 662-7764

TELEPHONE
CONSOLIDATED COMMUNICATIONS
1575 GREENLAND ROAD
GREENLAND, NH 03840
(603) 427-5525
CONTACT: JOE CONSIDINE

SURVEYOR
HAYES ENGINEERS, INC.
603 SALEM STREET
WAKEFIELD, MA 01880
(781) 246-2800

WETLAND CONSULTANT
MISSION WETLAND & ECOLOGICAL SERVICES, LLC
P.O. BOX 4028
PORTSMOUTH, NH 03802
CONTACT: SERGIO BONILLA, PWS, CWS


CABLE TV
COMCAST COMMUNICATION CORPORATION
334-B CALEF HIGHWAY
EPPING, NH 03042-2325
(603) 679-5695

PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228	APPROVED - CANDIA, NH PLANNING BOARD
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169	
TOTAL LOT AREA ± 72 ACRES	

DATE:

Design: JPT Draft: KDR Date: 03/25/25
Checked: BWG Scale: AS NOTED Project No.: 24025
Drawing Name: 24025-PLAN.dwg

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	COVER SHEET
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.	CS
SHEET 1 OF 30	JBE PROJECT NO. 24025

DIAMOND HILL SUBDIVISION, CANDIA, NH
JBE # 24025 REVISION 0.9/6/2024




GENERAL LEGEND

EXISTING	PROPOSED	DESCRIPTION
---	---	PROPERTY LINES
---	---	SETBACK LINES
---	---	FRESHWATER WETLANDS LINE
---	---	EASEMENT
---	---	EDGE OF PAVEMENT
---	---	IRON PIPE/IRON ROD
---	---	DRILL HOLE
---	---	IRON ROD/DRILL HOLE
---	---	STONE/GRANITE BOUND
---	---	FRESHWATER WETLANDS

PROJECT PARCEL
TOWN OF CANDIA
TAX MAP 409, LOT 228

APPLICANT/OWNER
AV DEVELOPMENT, LLC
2 GRANITE RAIL COURT
QUINCY, MA 02169

TOTAL LOT AREA
±72 ACRES




SUBDIVISION NOTES:


- THE INTENT OF THIS PLAN IS TO SUBDIVIDE MAP 409, LOT 228 INTO NINE (9) SINGLE FAMILY RESIDENTIAL LOTS WITH ONSITE WATER AND SEPTIC.
- JONES & BEACH ENGINEERS, INC. IS RESPONSIBLE FOR ABUTTER INFORMATION DEPICTED. ALL ABUTTER INFORMATION WAS DERIVED FROM CANDIA, NH VISION GOVERNMENT SOLUTIONS WEBSITE AND CANDIA, NH TAX MAPS.
- THE FOLLOWING WAIVERS HAVE BEEN REQUESTED FROM THE SUBDIVISION REGULATIONS:
A) WAIVER TO SECTION 10.06.C OF THE SUBDIVISION REGULATIONS.
- NHDES APPROVAL FOR SUBDIVISION PERMIT NO. , DATED
NHDES ALTERATION OF TERRAIN PERMIT NO. , DATED
NHDES WETLANDS BUREAU PERMIT NO. , DATED
- THIS PLAN SET HAS BEEN PREPARED BY JONES & BEACH ENGINEERS, INC., FOR MUNICIPAL AND STATE APPROVALS AND FOR CONSTRUCTION BASED ON DATA OBTAINED FROM ON-SITE FIELD SURVEY AND EXISTING MUNICIPAL RECORDS. THROUGHOUT THE CONSTRUCTION PROCESS, THE CONTRACTOR SHALL INFORM THE ENGINEER IMMEDIATELY OF ANY FIELD DISCREPANCY FROM DATA AS SHOWN ON THE DESIGN PLANS, INCLUDING ANY UNFORESEEN CONDITIONS, SUBSURFACE OR OTHERWISE, FOR EVALUATION AND RECOMMENDATIONS. ANY CONTRADICTION BETWEEN ITEMS ON THIS PLAN/PLAN SET, OR BETWEEN THE PLANS AND ON-SITE CONDITIONS, MUST BE RESOLVED BEFORE RELATED CONSTRUCTION HAS BEEN INITIATED.
- BOUNDARY: HAYES ENGINEERING, INC. IS RESPONSIBLE FOR THE PERIMETER DETERMINATION OF THE NORTHERLY PORTION OF THE SUBJECT PREMISES, DEPICTED ON A PLAN ENTITLED "BOUNDARY SURVEY OF LAND, CANDIA, NEW HAMPSHIRE" RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS AS PLAN D-44484. HAYES ENGINEERING, INC. IS NOT RESPONSIBLE FOR THE DESIGN OF THE PROPOSED SUBDIVISION.
- DATUM: THE VERTICAL DATUM IS BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) BASED UPON MACORS REAL-TIME NETWORK NAD 83 (2011) (EPOCH 2010.00) DATUM USING GEOID 2016 FOR ORTHOMETRIC HEIGHTS. THE HORIZONTAL DATUM IS NAD83 NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM BASED ON GPS OBSERVATIONS.
- THE PROPOSED LIMITS OF IMPROVEMENT ON THE SUBJECT PROPERTY IS NOT LOCATED WITHIN FEDERALLY DESIGNATED FLOOD HAZARD ZONE. REFERENCE FEMA COMMUNITY PANEL NO. 33015C0170E, DATED MAY 17, 2005.
- ALL CONSTRUCTION ACTIVITIES SHALL BE PERFORMED IN ACCORDANCE WITH THE STORMWATER POLLUTION PREVENTION PLAN (S.W.P.P.), THIS DOCUMENT IS TO BE KEPT ONSITE AT ALL TIMES AND UPDATED AS REQUIRED.
- PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER, ARCHITECT AND/OR OWNER, IN ORDER TO OBTAIN AND/OR PAY ALL THE NECESSARY LOCAL PERMITS, FEES AND BONDS.
- ALL CONSTRUCTION WILL CONFORM TO TOWN STANDARDS AND REGULATIONS, AND NHDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, WHICHEVER IS MORE STRINGENT.
- ALL CONSTRUCTION ACTIVITIES SHALL CONFORM TO LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) RULES AND REGULATIONS.
- GRANITE BOUNDS TO BE SET AT ALL ROADWAY POINTS OF CURVATURE AND TANGENCY. IRON RODS WITH SURVEY CAPS TO BE SET AT ALL PROPERTY CORNERS AND ANGLE POINTS, UNLESS OTHERWISE INDICATED. ALL MONUMENTS SET ARE 5/8" IRON RODS WITH ALUMINUM CAPS "DO NOT DISTURB" AS SHOWN.
- THE LIMITS OF JURISDICTIONAL WETLANDS WERE DELINEATED BY SERGIO BONILLA, CWS DURING SUMMER, 2022, IN ACCORDANCE WITH THE FOLLOWING GUIDANCE DOCUMENTS:
a. THE CORPUS OF ENGINEERS FEDERAL MANUAL FOR IDENTIFYING AND DELINEATING JURISDICTIONAL WETLANDS.
b. THE NORTH CENTRAL & NORTHEAST REGIONAL SUPPLEMENT TO THE FEDERAL MANUAL.
c. THE CURRENT VERSION OF THE FIELD INDICATORS FOR IDENTIFYING HYDRIC SOILS IN NEW ENGLAND, AS PUBLISHED BY THE NEW ENGLAND INTERSTATE WATER POLLUTION CONTROL COMMISSION AND/OR THE CURRENT VERSION OF THE FIELD INDICATORS OF HYDRIC SOILS IN THE UNITED STATES, AS PUBLISHED BY THE USDA, NRCS, AS APPROPRIATE.
d. THE CURRENT NATIONAL LIST OF PLANT SPECIES THAT OCCUR IN WETLANDS, AS PUBLISHED BY THE US FISH AND WILDLIFE SERVICE.
- LANDOWNERS ARE RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL WETLAND REGULATIONS, INCLUDING PERMITTING REQUIRED UNDER THESE REGULATIONS.
- UPON APPROVAL BY THE TOWN, THE PROPOSED ROAD WILL BE CONVEYED TO THE TOWN.
- ALL UTILITIES SHALL BE INSTALLED UNDERGROUND.
- ALL LOTS ARE SUBJECT TO AN EASEMENT ALONG FRONTAGE FOR SLOPE, GRADING, DRAINAGE AND UTILITIES, SEE SHEETS A2 THRU A5 FOR EXACT WIDTH.
- ALL BOOK AND PAGE NUMBERS REFER TO THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.
- THE TAX MAP AND LOT NUMBERS AND ABUTTING OWNERS ARE BASED ON THE TOWN OF CANDIA TAX RECORDS AND ARE SUBJECT TO CHANGE.
- RESEARCH WAS PERFORMED AT THE TOWN OF CANDIA ASSESSORS OFFICE AND THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.
- THIS SURVEY IS NOT A CERTIFICATION OF OWNERSHIP OR TITLE OF LANDS SHOWN. OWNERSHIP AND ENCUMBRANCES ARE MATTERS OF TITLE EXAMINATION NOT OF A BOUNDARY SURVEY. THE INTENT OF THIS PLAN IS TO RETRACE THE BOUNDARY LINES OF DEEDS REFERENCED HEREON. OWNERSHIP OF ADJOINING PROPERTIES IS ACCORDING TO ASSESSOR'S RECORDS. THIS PLAN MAY OR MAY NOT INDICATE ALL ENCUMBRANCES EXPRESSED, IMPLIED OR PRESCRIPTIVE.
- ANY USE OF THIS PLAN AND/OR ACCOMPANYING DESCRIPTIONS SHOULD BE DONE WITH LEGAL COUNSEL TO BE CERTAIN THAT TITLES ARE CLEAR, THAT INFORMATION IS CURRENT, AND THAT ANY NECESSARY CERTIFICATES ARE IN PLACE FOR A PARTICULAR CONVEYANCE, OR OTHER USES.
- ALL PROPOSED LOTS CONTAIN A MINIMUM OF 1.5 ACRES OF CONTIGUOUS NON-POORLY DRAINED SOILS.

CERTIFICATION:

I CERTIFY THAT THIS PLAT WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN UNADJUSTED LINEAR ERROR OF CLOSURE THAT EXCEEDS BOTH THE MINIMUM OF 1:10,000 AS DEFINED IN SECTION 503.04 OF THE NEW HAMPSHIRE CODE OF ADMINISTRATIVE RULES AND THE MINIMUM OF 1:15,000 AS DEFINED IN SECTION 4.2 OF THE N.H.L.S.A. ETHICS AND STANDARDS.
THIS SURVEY CONFORMS TO A CATEGORY 1 CONDITION 1 SURVEY AS DEFINED IN SECTION 4.1 OF THE N.H.L.S.A. ETHICS AND STANDARDS.



THOMAS F. WINSLOW, LLS 654 DATE:
ON BEHALF OF HAYES ENGINEERS, INC.



ZONE	RESIDENTIAL (R)
MINIMUM LOT AREA	3 ACRES (130,880 S.F.)
MINIMUM LOT WIDTH/FRONTAGE	200'
FRONT SETBACK	50'
SIDE SETBACK	25'
REAR SETBACK	25'
MAXIMUM BUILDING HEIGHT	35'

TAX MAP 409 LOT 226-1
WEISS, RONALD & PTACEK
114 PATTEN HILL ROAD
CANDIA, NH 03034
BK 3086 PG 0172
RESIDENTIAL

REMAINING PORTION
UNBUILDABLE LOT
OF TAX MAP 409 LOT 228
32± ACRES BY SCALE

TAX MAP 409 LOT 157
HEPFINGER, GALE M.
150 DIAMOND HILL ROAD
CANDIA, NH 03034
BK 5867 PG 2717
RESIDENTIAL

TAX MAP 409 LOT 155-1
STATE OF NEW HAMPSHIRE, TRAILS
172 PEMBROKE ROAD
P.O. BOX 1856
CONCORD, NH 03302-1856
BK 0 PG 0
RESIDENTIAL

TAX MAP 409 LOT 226-3
ROSS, EILEEN, TRUSTEE
C/O EILEEN ROSS REV TRUST
132 PATTEN HILL ROAD
CANDIA, NH 03034
BK 4057 PG 0729
RESIDENTIAL

TAX MAP 409 LOT 227
AUDUBON SOCIETY OF NH
3 SILK FARM ROAD
CONCORD, NH 03301
BK 0 PG 0
RESIDENTIAL

TAX MAP 409 LOT 228-3
MARTINEAU, KATHLEEN & SONDRRA
168 PATTEN HILL ROAD
CANDIA, NH 03034
BK 6117 PG 1335
RESIDENTIAL

TAX MAP 409 LOT 228-2
PAGE, CHRISTOPHER M & KATHLEEN W
176 PATTEN HILL ROAD
CANDIA, NH 03034
BK 6130 PG 1576
RESIDENTIAL

TAX MAP 409 LOT 155
KLEINER, TIMOTHY A
106 FOREST DRIVE
AUBURN, NH 03032
BK 6206 PG 835
RESIDENTIAL

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
REV.	DATE	REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885
Civil Engineering Services
603-772-4746
E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: **OVERVIEW SUBDIVISION PLAN**
MAP 409, LOT 228




Project: **DIAMOND HILL SUBDIVISION**
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH

Owner of Record: **AV DEVELOPMENT, LLC**
2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No. **A1**


SHEET 2 OF 30
JBE PROJECT NO. 24025

Hayes Engineering, Inc.
Civil Engineers & Land Surveyors
603 Salem Street
Wakefield, MA 01880
Telephone: 781.246.2800
www.hayeseng.com
Date: February 20, 2025




ZONING SUMMARY	
ZONE	RESIDENTIAL (R)
MINIMUM LOT AREA	3 ACRES (130,680 S.F.)
MINIMUM LOT WIDTH/FRONTAGE	200'
FRONT SETBACK	50'
SIDE SETBACK	25'
REAR SETBACK	25'
MAXIMUM BUILDING HEIGHT	35'

CERTIFICATION:
 I CERTIFY THAT THIS PLAT WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN UNADJUSTED LINEAR ERROR OF CLOSURE THAT EXCEEDS BOTH THE MINIMUM OF 1:10,000 AS DEFINED IN SECTION 503.04 OF THE NEW HAMPSHIRE CODE OF ADMINISTRATIVE RULES AND THE MINIMUM OF 1:15,000 AS DEFINED IN SECTION 4.2 OF THE N.H.L.S.A. ETHICS AND STANDARDS.
 THIS SURVEY CONFORMS TO A CATEGORY 1 CONDITION 1 SURVEY AS DEFINED IN SECTION 4.1 OF THE N.H.L.S.A. ETHICS AND STANDARDS.



THOMAS F. WINSLOW, LLS 654
 ON BEHALF OF HAYES ENGINEERS, INC. DATE: _____



PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Hayes
 Hayes Engineering, Inc.
 Civil Engineers &
 Land Surveyors
 603 Salem Street
 Wakefield, MA 01880
 Telephone: 781.246.2800
 www.hayeseng.com
 Date: February 20, 2025




Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
REV.	DATE	REVISION	BY

Designed and Produced in NH
J/B Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. Stratham, NH 03885
 Civil Engineering Services
 603-772-4746
 E-MAIL: JBE@JONESANDBEACH.COM


Plan Name:	SUBDIVISION PLAN MAP 409, LOT 228
Project:	MAP 409 / LOT 228: DIAMOND HILL SUBDIVISION DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
A2
 SHEET 3 OF 30
 JBE PROJECT NO. 24025




ZONING SUMMARY	
ZONE	RESIDENTIAL (R)
MINIMUM LOT AREA	3 ACRES (130,680 S.F.)
MINIMUM LOT WIDTH/FRONTAGE	200'
FRONT SETBACK	50'
SIDE SETBACK	25'
REAR SETBACK	25'
MAXIMUM BUILDING HEIGHT	35'

CERTIFICATION:
I CERTIFY THAT THIS PLAT WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN UNADJUSTED LINEAR ERROR OF CLOSURE THAT EXCEEDS BOTH THE MINIMUM OF 1:10,000 AS DEFINED IN SECTION 503.04 OF THE NEW HAMPSHIRE CODE OF ADMINISTRATIVE RULES AND THE MINIMUM OF 1:15,000 AS DEFINED IN SECTION 4.2 OF THE N.H.L.S.A. ETHICS AND STANDARDS.
THIS SURVEY CONFORMS TO A CATEGORY 1 CONDITION 1 SURVEY AS DEFINED IN SECTION 4.1 OF THE N.H.L.S.A. ETHICS AND STANDARDS.



THOMAS F. WINSLOW, LLS 654
ON BEHALF OF HAYES ENGINEERS, INC. DATE:



PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Hayes
Hayes Engineering, Inc.
Civil Engineers &
Land Surveyors
603 Salem Street
Wakefield, MA 01880
Telephone: 781.246.2800
www.hayeseng.com
Date: February 20, 2025

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		




REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.
Civil Engineering Services
85 Portsmouth Ave. PO Box 219 Stratham, NH 03885
603-772-4746
E-MAIL: JBE@JONESANDBEACH.COM


Plan Name:	SUBDIVISION PLAN MAP 409, LOT 228
Project:	MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
A3
SHEET 4 OF 30
JBE PROJECT NO. 24025




ZONING SUMMARY	
ZONE	RESIDENTIAL (R)
MINIMUM LOT AREA	3 ACRES (130,680 S.F.)
MINIMUM LOT WIDTH/FRONTAGE	200'
FRONT SETBACK	50'
SIDE SETBACK	25'
REAR SETBACK	25'
MAXIMUM BUILDING HEIGHT	35'

CERTIFICATION:
 I CERTIFY THAT THIS PLAT WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN UNADJUSTED LINEAR ERROR OF CLOSURE THAT EXCEEDS BOTH THE MINIMUM OF 1:10,000 AS DEFINED IN SECTION 503.04 OF THE NEW HAMPSHIRE CODE OF ADMINISTRATIVE RULES AND THE MINIMUM OF 1:15,000 AS DEFINED IN SECTION 4.2 OF THE N.H.L.S.A. ETHICS AND STANDARDS.
 THIS SURVEY CONFORMS TO A CATEGORY 1 CONDITION 1 SURVEY AS DEFINED IN SECTION 4.1 OF THE N.H.L.S.A. ETHICS AND STANDARDS.



THOMAS F. WINSLOW, LLS 654 DATE:
 ON BEHALF OF HAYES ENGINEERS, INC.



PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Hayes
 Hayes Engineering, Inc.
 Civil Engineers &
 Land Surveyors
 603 Salem Street
 Wakefield, MA 01880
 Telephone: 781.246.2800
 www.hayeseng.com
 Date: February 20, 2025



Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY

Designed and Produced in NH
J/B Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	SUBDIVISION PLAN MAP 409, LOT 228
Project:	MAP 409 / LOT 228: DIAMOND HILL SUBDIVISION DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
A4
 SHEET 5 OF 30
 JBE PROJECT NO. 24025




ZONING SUMMARY

ZONE	RESIDENTIAL (R)
MINIMUM LOT AREA	3 ACRES (130,680 S.F.)
MINIMUM LOT WIDTH/FRONTAGE	200'
FRONT SETBACK	50'
SIDE SETBACK	25'
REAR SETBACK	25'
MAXIMUM BUILDING HEIGHT	35'

CERTIFICATION:
 I CERTIFY THAT THIS PLAT WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN UNADJUSTED LINEAR ERROR OF CLOSURE THAT EXCEEDS BOTH THE MINIMUM OF 1:10,000 AS DEFINED IN SECTION 503.04 OF THE NEW HAMPSHIRE CODE OF ADMINISTRATIVE RULES AND THE MINIMUM OF 1:15,000 AS DEFINED IN SECTION 4.2 OF THE N.H.L.S.A. ETHICS AND STANDARDS.
 THIS SURVEY CONFORMS TO A CATEGORY 1 CONDITION 1 SURVEY AS DEFINED IN SECTION 4.1 OF THE N.H.L.S.A. ETHICS AND STANDARDS.

SIGNATURE: **THOMAS F. WINSLOW, LLS 654**
 ON BEHALF OF HAYES ENGINEERS, INC.



PROJECT PARCEL
 TOWN OF CANDIA
 TAX MAP 409, LOT 228

APPLICANT/OWNER
 AV DEVELOPMENT, LLC
 2 GRANITE RAIL COURT
 QUINCY, MA 02169

TOTAL LOT AREA
 ± 72 ACRES

Hayes Engineering, Inc.
 Civil Engineers &
 Land Surveyors
 603 Salem Street
 Wakefield, MA 01880
 Telephone: 781.246.2800
 www.hayeseng.com
 Date: February 20, 2025

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	


Designed and Produced in NH
Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219
 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	SUBDIVISION PLAN MAP 409, LOT 228
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169


DRAWING No.
A5
 SHEET 6 OF 30
 JBE PROJECT NO. 24025

GENERAL LEGEND

EXISTING	DESCRIPTION
---	PROPERTY LINES
---	SETBACK LINES
---	CENTERLINE
---	FRESHWATER WETLANDS LINE
---	VERNAL POOL LINE
---	STONEWALL
---	SOIL BOUNDARY
---	MAJOR CONTOUR
---	MINOR CONTOUR
---	EDGE OF PAVEMENT
---	DRAINAGE LINE
---	OVERHEAD ELECTRIC
---	UNDERDRAIN
---	IRON PIPE/IRON ROD
---	DRILL HOLE
---	STONE/GRAVITE BOUND
---	UTILITY POLE
---	FRESHWATER WETLANDS
---	STEEP SLOPES



- EXISTING CONDITIONS NOTES:**
- BOUNDARY: HAYES ENGINEERING, INC. IS RESPONSIBLE FOR THE PERIMETER DETERMINATION OF THE NORTHERLY PORTION OF THE SUBJECT PREMISES, DEPICTED ON A PLAN ENTITLED "BOUNDARY SURVEY OF LAND, CANDIA, NEW HAMPSHIRE" RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS AS PLAN D-44484.
 - JONES & BEACH ENGINEERS, INC. IS RESPONSIBLE FOR ABUTTER INFORMATION DEPICTED. ALL ABUTTER INFORMATION WAS DERIVED FROM CANDIA, NH VISION GOVERNMENT SOLUTIONS WEBSITE AND CANDIA, NH TAX MAPS.
 - UNDERGROUND FACILITIES, UTILITIES AND STRUCTURES HAVE BEEN PLOTTED FROM FIELD OBSERVATION AND THEIR LOCATION MUST BE CONSIDERED APPROXIMATE ONLY. NEITHER JONES & BEACH ENGINEERS, INC. NOR ANY OF THE EMPLOYEES TAKE RESPONSIBILITY FOR THE LOCATION OF ANY UNDERGROUND STRUCTURES OR UTILITIES NOT SHOWN THAT MAY EXIST. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE ALL UNDERGROUND STRUCTURES AND/OR UTILITIES LOCATED PRIOR TO EXCAVATION WORK BY CALLING 1-888-DIG-SAFE (1-888-344-7233).
 - DATUM: THE VERTICAL DATUM IS BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) BASED UPON MACORS REAL-TIME NETWORK NAD 83 (2011) (EPOCH 2010.00) DATUM USING GEOID 2018 FOR ORTHOMETRIC HEIGHTS. THE HORIZONTAL DATUM IS NAD83 NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM BASED ON GPS OBSERVATIONS.
 - TOPOGRAPHY: THIS PLAN IS BASED OFF ACTUAL ON-THE-GROUND SURVEYS CONDUCTED BY HAYES ENGINEERING BETWEEN JULY 2022 AND JULY 2024 AND SUPPLEMENTED WITH CONTOURS OBTAINED FROM NOAA ONLINE DATA ACCESS VIEWER USING THE 2019-2020 USGS LIDAR: NH COASTAL (Q11) SURVEY.
 - THE PROPOSED LIMITS OF IMPROVEMENT ON THE SUBJECT PROPERTY IS NOT LOCATED WITHIN FEDERALLY DESIGNATED FLOOD HAZARD ZONE. REFERENCE FEMA COMMUNITY PANEL NO. 3301SC0170E, DATED MAY 16, 2005.
 - THE LIMITS OF JURISDICTIONAL WETLANDS WERE DELINEATED BY SERGIO BONILLA, CWS DURING SUMMER, 2022, IN ACCORDANCE WITH THE FOLLOWING GUIDANCE DOCUMENTS:
 - THE CORPS OF ENGINEERS FEDERAL MANUAL FOR IDENTIFYING AND DELINEATING JURISDICTIONAL WETLANDS.
 - THE NORTH CENTRAL & NORTHEAST REGIONAL SUPPLEMENT TO THE FEDERAL MANUAL.
 - THE CURRENT VERSION OF THE FIELD INDICATORS FOR IDENTIFYING HYDRIC SOILS IN NEW ENGLAND, AS PUBLISHED BY THE NEW ENGLAND INTERSTATE WATER POLLUTION CONTROL COMMISSION AND/OR THE CURRENT VERSION OF THE FIELD INDICATORS OF HYDRIC SOILS IN THE UNITED STATES, AS PUBLISHED BY THE USDA, NRCS, AS APPROPRIATE.
 - THE CURRENT NATIONAL LIST OF PLANT SPECIES THAT OCCUR IN WETLANDS, AS PUBLISHED BY THE US FISH AND WILDLIFE SERVICE.
 - SITE-SPECIFIC SOIL MAPPING WAS PERFORMED BY JOHN HAYES III (CSS). DURING FALL, 2024, AND IS BASED ON THE STANDARDS OF SITE-SPECIFIC SOIL MAPPING STANDARDS FOR NEW HAMPSHIRE AND VERMONT, VERSION 2.0 (1999: SOCIETY OF SOIL SCIENTISTS OF NORTHERN NEW ENGLAND). THE MAP IS WITHIN THE TECHNICAL STANDARDS OF THE NATIONAL COOPERATIVE SOIL SURVEY. IT IS A SPECIAL PURPOSE PRODUCT INTENDED FOR THE USE(S) REQUIRING THE SITE SPECIFIC SOIL SURVEY AND IS PRODUCED BY A CERTIFIED SOIL SCIENTIST. IT IS NOT A PRODUCT OF THE USDA NATURAL RESOURCES CONSERVATION SERVICE. A NARRATIVE REPORT IS A COMPONENT OF THE MAP.
 - A TEMPORARY CULVERT AND ROADBED SHALL BE IN PLACE PRIOR TO ANY USE OF A WETLAND CROSSING.
 - WETLAND IMPACTS SHALL NOT OCCUR UNTIL ALL PERMITS HAVE BEEN ACQUIRED AND IMPACT MITIGATION REQUIREMENTS HAVE BEEN SATISFIED.
 - TEST PITS PERFORMED BY ANTHONY JONES, JONES & BEACH ENGINEERS, INC., 10/11/24.
 - WETLAND BOUNDARIES AND CONSTRUCTION LIMITS ARE TO BE CLEARLY MARKED PRIOR TO THE START OF CONSTRUCTION.
 - JONES AND BEACH ENGINEERS, INC. IS RESPONSIBLE FOR ABUTTING HOME OWNER INFORMATION SHOWN ON THESE PLANS.



Hayes
 Hayes Engineering, Inc.
 Civil Engineers &
 Land Surveyors
 603 Salem Street
 Wakefield, MA 01880
 Telephone: 781.246.2800
 www.hayeseng.com
 Date: February 20, 2025

PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
REV.	DATE	REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885

Civil Engineering Services

603-772-4746



E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: OVERVIEW EXISTING CONDITIONS PLAN
Project: DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record: AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No. C1 SHEET 7 OF 30 JBE PROJECT NO. 24025
--

GENERAL LEGEND

EXISTING	DESCRIPTION
	PROPERTY LINES
	SETBACK LINES
	CENTERLINE
	FRESHWATER WETLANDS LINE
	VERNAL POOL LINE
	STONEWALL
	SOIL BOUNDARY
	MAJOR CONTOUR
	MINOR CONTOUR
	EDGE OF PAVEMENT
	DRAINAGE LINE
	OVERHEAD ELECTRIC
	UNDERDRAIN
	IRON PIPE/IRON ROD
	DRILL HOLE
	STONE/GRAVITE BOUND
	UTILITY POLE
	LIGHT POLES
	FRESHWATER WETLANDS
	STEEP SLOPES




EXISTING CONDITIONS NOTES:

- BOUNDARY: HAYES ENGINEERING, INC. IS RESPONSIBLE FOR THE PERIMETER DETERMINATION OF THE NORTHERLY PORTION OF THE SUBJECT PREMISES, DEPICTED ON A PLAN ENTITLED "BOUNDARY SURVEY OF LAND, CANDIA, NEW HAMPSHIRE" RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS AS PLAN D-44484.
- JONES & BEACH ENGINEERS, INC. IS RESPONSIBLE FOR ABUTTER INFORMATION DEPICTED. ALL ABUTTER INFORMATION WAS DERIVED FROM CANDIA, NH VISION GOVERNMENT SOLUTIONS WEBSITE AND CANDIA, NH TAX MAPS.
- UNDERGROUND FACILITIES, UTILITIES AND STRUCTURES HAVE BEEN PLOTTED FROM FIELD OBSERVATION AND THEIR LOCATION MUST BE CONSIDERED APPROXIMATE ONLY. NEITHER JONES & BEACH ENGINEERS, INC., NOR ANY OF THEIR EMPLOYEES TAKE RESPONSIBILITY FOR THE LOCATION OF ANY UNDERGROUND STRUCTURES OR UTILITIES NOT SHOWN THAT MAY EXIST. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE ALL UNDERGROUND STRUCTURES AND/OR UTILITIES LOCATED PRIOR TO EXCAVATION WORK BY CALLING 1-888-DIG-SAFE (1-888-344-7233).
- DATUM: THE VERTICAL DATUM IS BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) BASED UPON MACORS REAL-TIME NETWORK NAD 83 (2011) (EPOCH 2010.00) DATUM USING GEOID 2018 FOR ORTHOMETRIC HEIGHTS. THE HORIZONTAL DATUM IS NAD83 NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM BASED ON GPS OBSERVATIONS.
- TOPOGRAPHY: THIS PLAN IS BASED OFF ACTUAL ON-THE-GROUND SURVEYS CONDUCTED BY HAYES ENGINEERING BETWEEN JULY 2022 AND JULY 2024 AND SUPPLEMENTED WITH CONTOURS OBTAINED FROM NOAA ONLINE DATA ACCESS VIEWER USING THE 2019-2020 USGS LIDAR: NH COASTAL (Q1) SURVEY.
- THE PROPOSED LIMITS OF IMPROVEMENT ON THE SUBJECT PROPERTY IS NOT LOCATED WITHIN FEDERALLY DESIGNATED FLOOD HAZARD ZONE. REFERENCE FEMA COMMUNITY PANEL NO. 33015C0170E, DATED MAY 16, 2005.
- THE LIMITS OF JURISDICTIONAL WETLANDS WERE DELINEATED BY SERGIO BONILLA, CWS DURING SUMMER, 2022, IN ACCORDANCE WITH THE FOLLOWING GUIDANCE DOCUMENTS:
 - THE CORPS OF ENGINEERS FEDERAL MANUAL FOR IDENTIFYING AND DELINEATING JURISDICTIONAL WETLANDS.
 - THE NORTH CENTRAL & NORTHEAST REGIONAL SUPPLEMENT TO THE FEDERAL MANUAL.
 - THE CURRENT VERSION OF THE FIELD INDICATORS FOR IDENTIFYING HYDRIC SOILS IN NEW ENGLAND, AS PUBLISHED BY THE NEW ENGLAND INTERSTATE WATER POLLUTION CONTROL COMMISSION AND/OR THE CURRENT VERSION OF THE FIELD INDICATORS OF HYDRIC SOILS IN THE UNITED STATES, AS PUBLISHED BY THE USDA, NRCS, AS APPROPRIATE.
 - THE CURRENT NATIONAL LIST OF PLANT SPECIES THAT OCCUR IN WETLANDS, AS PUBLISHED BY THE US FISH AND WILDLIFE SERVICE.
- SITE-SPECIFIC SOIL MAPPING WAS PERFORMED BY JOHN HAYES III (CSS), DURING FALL, 2024, AND IS BASED ON THE STANDARDS OF SITE-SPECIFIC SOIL MAPPING STANDARDS FOR NEW HAMPSHIRE AND VERMONT, VERSION 2.0 (1998; SOCIETY OF SOIL SCIENTISTS OF NORTHERN NEW ENGLAND). THE MAP IS WITHIN THE TECHNICAL STANDARDS OF THE NATIONAL COOPERATIVE SOIL SURVEY. IT IS A SPECIAL PURPOSE PRODUCT INTENDED FOR THE USE(S) REQUIRING THE SITE SPECIFIC SOIL SURVEY AND IS PRODUCED BY A CERTIFIED SOIL SCIENTIST. IT IS NOT A PRODUCT OF THE USDA NATURAL RESOURCES CONSERVATION SERVICE. A NARRATIVE REPORT IS A COMPONENT OF THE MAP.
- A TEMPORARY CULVERT AND ROADBED SHALL BE IN PLACE PRIOR TO ANY USE OF A WETLAND CROSSING.
- WETLAND IMPACTS SHALL NOT OCCUR UNTIL ALL PERMITS HAVE BEEN ACQUIRED AND IMPACT MITIGATION REQUIREMENTS HAVE BEEN SATISFIED.
- TEST PITS PERFORMED BY ANTHONY JONES, JONES & BEACH ENGINEERS, INC., 10/11/24.
- WETLAND BOUNDARIES AND CONSTRUCTION LIMITS ARE TO BE CLEARLY MARKED PRIOR TO THE START OF CONSTRUCTION.

PROJECT PARCEL
TOWN OF CANDIA
TAX MAP 409, LOT 228

APPLICANT/OWNER
AV DEVELOPMENT, LLC
2 GRANITE RAIL COURT
QUINCY, MA 02169

TOTAL LOT AREA
± 72 ACRES



Hoyes Hayes Engineering, Inc.
Civil Engineers &
Land Surveyors
603 Salem Street
Wakefield, MA 01880
Telephone: 781.246.2800
www.hoyeseng.com
Date: February 20, 2025

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG

Designed and Produced in NH




J/B Jones & Beach Engineers, Inc.
Civil Engineering Services

85 Portsmouth Ave. PO Box 219 Stratham, NH 03885

603-772-4746
E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: OVERVIEW EXISTING CONDITIONS PLAN
Project: DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record: AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.	C1B
SHEET 8 OF 30	JBE PROJECT NO. 24025



SOILS LEGEND:

SITE SPECIFIC SOILS WERE COMPLETED BY JOHN HAYES III, CSS PER THE GUIDELINES OUTLINED IN THE SITE SPECIFIC MAPPING STANDARDS FOR VERMONT AND NEW HAMPSHIRE, VERSION 4 DATED NOVEMBER 2024. ON SITE MAPPING WAS CONDUCTED OCTOBER 28-30, 2024.

85RK B-E	HOLLIS SERIES	WELL DRAINED, HYDROLOGIC GROUP D
135 B-D	CHATFIELD VAIRANCE/NEWFIELDS COMPLEX	MODERATELY WELL DRAINED, HYDROLOGIC GROUP B
140RK B-E	CHATFIELD HOLLIS CANTON COMPLEX	WELL DRAINED, HYDROLOGIC GROUP B/D
141RK B-E	HOLLIS ROCK OUTCROP/CHATFIELD COMPLEX	WELL DRAINED, HYDROLOGIC GROUP B/D
184RK B-E	HOLLIS/CHATFIELD COMPLEX	WELL DRAINED, HYDROLOGIC GROUP B/D
445 B-D	NEWFIELDS	MODERATELY WELL DRAINED, HYDROLOGIC GROUP B
449 B-D	SCITUATE (VERY STONY)	MODERATELY WELL DRAINED, HYDROLOGIC GROUP C
515/P A-E	LEICESTER	POORLY DRAINED, HYDROLOGIC GROUP C

299(dcedb) A-B	UDORTHERTS	SATURATED HYDRAULIC CONDUCTIVITY HIGH, HYDROLOGIC GROUP B
550/RK(ccedb/d) B-D	UDORTHERTS	SATURATED HYDRAULIC CONDUCTIVITY HIGH TO VERY HIGH, HYDROLOGIC GROUP B/D
600/P (fcedc) A-C	UDORTHERTS	SATURATED HYDRAULIC CONDUCTIVITY MOD. HIGH TO HIGH, HYDROLOGIC GROUP C
600/VP (gcedd) B	UDORTHERTS	SATURATED HYDRAULIC CONDUCTIVITY MOD. HIGH TO HIGH, HYDROLOGIC GROUP D


SLOPE LEGEND:

SLOPE SYMBOL:	RANGE:
A	0-3%
B	3-8%
C	8-15%
D	15-25%
E	25-50%
F	>50%

GENERAL LEGEND

EXISTING	DESCRIPTION
---	PROPERTY LINES
---	SETBACK LINES
---	CENTERLINE
---	FRESHWATER WETLANDS LINE
---	VERNAL POOL LINE
---	STONEWALL
---	SOIL BOUNDARY
---	MAJOR CONTOUR
---	MINOR CONTOUR
---	EDGE OF PAVEMENT
---	DRAINAGE LINE
---	OVERHEAD ELECTRIC
---	UNDERDRAIN
---	IRON PIPE/IRON ROD
---	DRILL HOLE
---	STONE/GRANITE BOUND
---	UTILITY POLE
---	LIGHT POLES
---	FRESHWATER WETLANDS
---	STEEP SLOPES

GRAPHIC SCALE



PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Hayes
Hayes Engineering, Inc.
Civil Engineers &
Land Surveyors
603 Salem Street
Wakefield, MA 01880
Telephone: 781.246.2800
www.hayeseng.com
Date: February 20, 2025

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY



Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	EXISTING CONDITIONS PLAN
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.	C2
SHEET 9 OF 30	JBE PROJECT NO. 24025



Hayes
 Hayes Engineering, Inc.
 Civil Engineers &
 Land Surveyors
 603 Salem Street
 Wakefield, MA 01880
 Telephone: 781.246.2800
 www.hayeseng.com
 Date: February 20, 2025

PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY





Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219
 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	EXISTING CONDITIONS PLAN
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
C3
 SHEET 10 OF 30
 JBE PROJECT NO. 24025



Hayes Hayes Engineering, Inc.
Civil Engineers &
Land Surveyors
603 Salem Street
Wakefield, MA 01880
Telephone: 781.246.2800
www.hayeseng.com
Date: February 20, 2025

PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
REV.	DATE	REVISION	BY





Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
PO Box 219
Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	EXISTING CONDITIONS PLAN
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.	C4
SHEET 11 OF 30 JBE PROJECT NO. 24025	



PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Hayes
 Hayes Engineering, Inc.
 Civil Engineers &
 Land Surveyors
 603 Salem Street
 Wakefield, MA 01880
 Telephone: 781.246.2800
 www.hayeseng.com
 Date: February 20, 2025

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		

REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY


Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219
 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	EXISTING CONDITIONS PLAN
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
C5
 SHEET 12 OF 30
 JBE PROJECT NO. 24025



SITE NOTES:

- THE INTENT OF THIS PLAN IS TO SHOW PROPOSED FEATURES ON CANDIA, NH TAX MAP 409 LOT 228.
- THE FOLLOWING WAIVERS HAVE BEEN REQUESTED FROM THE SITE PLAN REVIEW REGULATIONS:
 - WAIVER TO SECTION 10.06.C OF THE SUBDIVISION REGULATIONS.
- NHDES APPROVAL FOR SUBDIVISION PERMIT NO. _____ DATED _____
 NHDES ALTERATION OF TERRAIN PERMIT NO. _____ DATED _____
 NHDES WETLANDS BUREAU PERMIT NO. _____ DATED _____
- THIS PLAN SET HAS BEEN PREPARED BY JONES & BEACH ENGINEERS, INC., FOR MUNICIPAL AND STATE APPROVALS AND FOR CONSTRUCTION BASED ON DATA OBTAINED FROM ON-SITE FIELD SURVEY AND EXISTING MUNICIPAL RECORDS. THROUGHOUT THE CONSTRUCTION PROCESS, THE CONTRACTOR SHALL INFORM THE ENGINEER IMMEDIATELY OF ANY FIELD DISCREPANCY FROM DATA AS SHOWN ON THE DESIGN PLANS, INCLUDING ANY UNFORESEEN CONDITIONS, SUBSURFACE OR OTHERWISE, FOR EVALUATION AND RECOMMENDATIONS. ANY CONTRADICTION BETWEEN ITEMS ON THIS PLAN/PLAN SET, OR BETWEEN THE PLANS AND ON-SITE CONDITIONS, MUST BE RESOLVED BEFORE RELATED CONSTRUCTION HAS BEEN INITIATED. CONTRACTOR TO ALWAYS CONTACT DIG SAFE PRIOR TO DIGGING ONSITE OR OFFSITE TO ENSURE SAFETY AND OBEY THE LAW.
- ALL CONSTRUCTION SHALL CONFORM TO TOWN STANDARDS AND REGULATIONS, AND NHDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, WHICHEVER IS MORE STRINGENT.
- THE PROPOSED LIMITS OF IMPROVEMENT ON THE SUBJECT PROPERTY IS NOT LOCATED WITHIN FEDERALLY DESIGNATED FLOOD HAZARD ZONE. REFERENCE FEMA COMMUNITY PANEL NO. 33015C0170E, DATED MAY 16, 2005.
- LANDOWNERS ARE RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL WETLAND REGULATIONS, INCLUDING PERMITTING REQUIRED UNDER THESE REGULATIONS.
- ALL CONSTRUCTION ACTIVITIES SHALL BE PERFORMED IN ACCORDANCE WITH THE STORMWATER POLLUTION PREVENTION PLAN (S.W.P.P.). THIS DOCUMENT IS TO BE KEPT ONSITE AT ALL TIMES AND UPDATED AS REQUIRED.
- PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER, ARCHITECT AND/OR OWNER, IN ORDER TO OBTAIN AND/OR PAY ALL THE NECESSARY LOCAL PERMITS, FEES AND BONDS.
- ALL STOP BARS SHALL BE 18" IN WIDTH IN A COLOR OF WHITE; ALL TRAFFIC ARROWS SHALL BE PAINTED IN A COLOR OF WHITE.
- ALL ARCHITECTURAL BLOCK RETAINING WALLS ARE TO BE DESIGNED AND STAMPED BY THE MANUFACTURER'S STRUCTURAL ENGINEER. CONTRACTOR TO COORDINATE WITH APPROVED MANUFACTURER PRIOR TO INSTALLATION.
- ALL CONSTRUCTION ACTIVITIES SHALL CONFORM TO LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) RULES AND REGULATIONS.
- ALL PRECAST CONCRETE PRODUCTS WILL BE SOURCED FROM MANUFACTURING FACILITIES IN COMPLIANCE WITH THE NATIONAL PRECAST CONCRETE ASSOCIATION (NPCA) PLANT CERTIFICATION PROGRAM. EVIDENCE OF COMPLIANCE WILL BE PROVIDED FOR THE CURRENT CALENDAR YEAR THE PRODUCTS WERE MANUFACTURED WITHIN.
- CONSTRUCTION START ANTICIPATED FALL '25 AND END LATE SPRING '26. AREAS SHALL BE STABILIZED PER TEMP. EROSION CONTROL NOTES, SHEET E1

ZONING SUMMARY	
ZONE	RESIDENTIAL (R)
MINIMUM LOT AREA	3 ACRES (130,680 S.F.)
MINIMUM LOT WIDTH/FRONTAGE	200'
FRONT SETBACK	50'
SIDE SETBACK	25'
REAR SETBACK	25'
MAXIMUM BUILDING HEIGHT	35'


APPROVED - CANDIA, NH
PLANNING BOARD

PROJECT PARCEL
TOWN OF CANDIA
TAX MAP 409, LOT 228

APPLICANT/OWNER
AV DEVELOPMENT, LLC
2 GRANITE RAIL COURT
QUINCY, MA 02169


TOTAL LOT AREA
± 72 ACRES

DATE: _____



Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: **OVERVIEW SITE PLAN**
MAP 409, LOT 228




Project: **DIAMOND HILL SUBDIVISION**
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH

Owner of Record: **AV DEVELOPMENT, LLC**
2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
C6


SHEET 13 OF 30
JBE PROJECT NO. 24025

03/26/2025




ZONING SUMMARY	
ZONE	RESIDENTIAL (R)
MINIMUM LOT AREA	3 ACRES (130,680 S.F.)
MINIMUM LOT WIDTH/FRONTAGE	200'
FRONT SETBACK	50'
SIDE SETBACK	25'
REAR SETBACK	25'
MAXIMUM BUILDING HEIGHT	35'

GENERAL LEGEND	
EXISTING	DESCRIPTION
---	PROPERTY LINES
---	SETBACK LINES
---	CENTERLINE
---	FRESHWATER WETLANDS LINE
---	VERNAL POOL LINE
---	STONEWALL
---	SOIL BOUNDARY
---	MAJOR CONTOUR
---	MINOR CONTOUR
---	EDGE OF PAVEMENT
---	DRAINAGE LINE
---	OVERHEAD ELECTRIC
---	UNDERDRAIN
---	IRON PIPE/IRON ROD
---	DRILL HOLE
---	STONE/GRANITE BOUND
---	UTILITY POLE
---	LIGHT POLES
---	FRESHWATER WETLANDS
---	STEEP SLOPES



APPROVED - CANDIA, NH PLANNING BOARD	
PROJECT PARCEL	TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA	± 72 ACRES
DATE:	

Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY





Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM


Plan Name:	SITE PLAN MAP_BLOCK_LOT
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
C7
SHEET 14 OF 30
JBE PROJECT NO. 24025



APPROVED - CANDIA, NH PLANNING BOARD	
PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228	
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169	
TOTAL LOT AREA ± 72 ACRES	
DATE: _____	

Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
REV.	DATE	REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885
 Civil Engineering Services
 603-772-4746
 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	SITE PLAN MAP_BLOCK_LOT
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169


DRAWING No.
C8
SHEET 15 OF 30
JBE PROJECT NO. 24025



GRADING AND DRAINAGE NOTES:


- UNDERGROUND FACILITIES, UTILITIES AND STRUCTURES HAVE BEEN PLOTTED FROM FIELD OBSERVATION AND THEIR LOCATION MUST BE CONSIDERED APPROXIMATE ONLY. NEITHER JONES & BEACH ENGINEERS, INC., NOR ANY OF THEIR EMPLOYEES TAKE RESPONSIBILITY FOR THE LOCATION OF ANY UNDERGROUND STRUCTURES AND/OR UTILITIES NOT SHOWN THAT MAY EXIST. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE ALL UNDERGROUND STRUCTURES AND/OR UTILITIES LOCATED PRIOR TO EXCAVATION WORK BY CALLING 888-DIG-SAFE (888-344-7233).
- VERTICAL DATUM: NH STATE PLANE. HORIZONTAL DATUM: NAD83
- ALL BENCHMARKS AND TOPOGRAPHY SHOULD BE FIELD VERIFIED BY THE CONTRACTOR.
- SITE GRADING SHALL NOT PROCEED UNTIL EROSION CONTROL MEASURES HAVE BEEN INSTALLED. SEE CONSTRUCTION SEQUENCE ON SHEET E1.
- PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR IS REQUIRED TO HAVE THE PROJECT'S LAND SURVEYOR STAKE OR FLAG CLEARING LIMITS. A MINIMUM OF 48 HOURS NOTICE IS REQUIRED.
- ALL ROOF DRAINS FROM BUILDING SHALL END 5' OUTSIDE THE BUILDING LIMITS AS SHOWN ON PLAN AND SHALL BE PROVIDED WITH A TEMPORARY PLUG AND WITNESS AT THE END. ALL EXTERIOR ROOF DOWNSPOUTS ARE TO BE INSTALLED WITH OVERFLOW DEVICES.
- ALL SWALES AND DETENTION PONDS ARE TO BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- PROPOSED RIM ELEVATIONS OF DRAINAGE STRUCTURES ARE APPROXIMATE. FINAL ELEVATIONS ARE TO BE SET FLUSH WITH FINISH GRADES.
- ALL SWALES AND ANY SLOPES GREATER THAN 3:1 SHALL BE STABILIZED WITH NORTH AMERICAN GREEN S75 EROSION CONTROL BLANKETS (OR AN EQUIVALENT APPROVED IN WRITING BY THE ENGINEER), UNLESS OTHERWISE SPECIFIED.
- ALL DRAINAGE AND SANITARY STRUCTURE INTERIOR DIAMETERS (4' MIN) SHALL BE DETERMINED BY THE MANUFACTURER BASED ON THE PIPE CONFIGURATIONS SHOWN ON THESE PLANS. CATCH BASINS SHALL HAVE 3' DEEP SUMPS WITH GREASE HOODS, UNLESS OTHERWISE NOTED.
- ALL DRAINAGE STRUCTURES SHALL BE PRECAST, UNLESS OTHERWISE SPECIFIED.
- ALL DRAINAGE STRUCTURES AND STORM SEWER PIPES SHALL MEET HEAVY DUTY TRAFFIC H20 LOADING AND SHALL BE INSTALLED ACCORDINGLY.
- IMMEDIATELY APPLY AND COMPACT STONE BASE FOR BUILDING PAD TO +/- 1/2" PRIOR TO EXCAVATING INTERIOR AND PERIMETER FOOTINGS.
- IN AREAS WHERE CONSTRUCTION IS PROPOSED ADJACENT TO ABUTTING PROPERTIES, THE CONTRACTOR SHALL INSTALL ORANGE CONSTRUCTION FENCING ALONG PROPERTY LINES IN ALL AREAS WHERE SILT FENCING IS NOT REQUIRED.
- ALL DRAINAGE PIPE SHALL BE NON-PERFORATED ADS N-12 OR APPROVED EQUAL.
- STONE INLET PROTECTION SHALL BE PLACED AT ALL CATCH BASINS. SEE DETAIL WITHIN THE DETAIL SHEETS.
- LAND DISTURBING ACTIVITIES SHALL NOT COMMENCE UNTIL APPROVAL TO DO SO HAS BEEN RECEIVED BY ALL GOVERNING AUTHORITIES. THE GENERAL CONTRACTOR SHALL STRICTLY ADHERE TO THE EPA SWPPP DURING CONSTRUCTION OPERATIONS.
- ALL EXPOSED AREAS SHALL BE SEEDED AS SPECIFIED WITHIN 3 DAYS OF FINAL GRADING AND ANYTIME CONSTRUCTION STOPS FOR LONGER THAN 3 DAYS.
- MAINTAIN EROSION CONTROL MEASURES AFTER EACH RAIN EVENT OF 0.5" OR GREATER IN A 24 HOUR PERIOD AND AT LEAST ONCE A WEEK.
- THIS PLAN SHALL NOT BE CONSIDERED ALL INCLUSIVE, AS THE GENERAL CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT SEDIMENT FROM LEAVING THE SITE.
- CONSTRUCTION VEHICLES SHALL UTILIZE THE STABILIZED CONSTRUCTION ENTRANCE TO THE EXTENT POSSIBLE THROUGHOUT CONSTRUCTION.
- IF INSTALLATION OF STORM DRAINAGE SYSTEM SHOULD BE INTERRUPTED BY WEATHER OR NIGHTFALL, THE PIPE ENDS SHALL BE COVERED WITH FILTER FABRIC.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE TO TAKE WHATEVER MEANS NECESSARY TO ESTABLISH PERMANENT SOIL STABILIZATION.
- SEDIMENT SHALL BE REMOVED FROM ALL SEDIMENT BASINS BEFORE THEY ARE 25% FULL.
- ALL WORK SHALL BE DONE IN STRICT ACCORDANCE WITH PROJECT SPECIFICATIONS.
- ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED, IF DEEMED NECESSARY BY ON-SITE INSPECTION BY ENGINEER AND/OR REGULATORY OFFICIALS.
- SEE ALSO EROSION AND SEDIMENT CONTROL SPECIFICATIONS ON SHEET E1.
- STUMPS, RUBBLE, ROAD CONSTRUCTION MATERIAL AND BRUSH SHALL BE DEPOSITED WITHIN AREAS DESIGNATED WASTING AREA. WASTING AREA SHALL NOT BE BELOW GROUND WATER ELEVATION AND SHALL BE CAPPED WITH 4" LOAM AND SEEDED.
- CONSTRUCTION OF ROADWAY INFRASTRUCTURE IS SCHEDULED TO BEGIN JUNE 1ST AND BE COMPLETED BY AUGUST 30TH. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME. AT NO TIME SHALL AN AREA IN EXCESS OF 5 ACRES BE EXPOSED AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.
- APPROXIMATELY 75' OF EXISTING STONEWALL TO BE REMOVED SHALL BE RELOCATED ALONG THE EXISTING PROPERTY LINE ADJACENT TO THE SECTION BEING REMOVED.
- STORMWATER PONDS AND BASINS SHALL BE MAINTAINED BY THE HOMEOWNER'S ASSOCIATION.
- ALL CULVERTS SHALL BE REINFORCED CONCRETE PIPE CLASS IV OR V. PIPE SHALL BE BELL AND SPIGOT OR TONGUE AND GROOVE TYPE WITH ELASTOMERIC OIL RESISTANT COMPRESSION RING JOINTING. ALL PIPES SHALL HAVE A MINIMUM COVER OF 3- FEET. MINIMUM CULVERT SIZE SHALL BE 15-INCHES. CLASS IV SHALL BE ALLOWED UNDER SHOULDER AND GREEN AREAS. CLASS V UNDER ROADWAYS AND FILL AREAS DEEPER THAN 15- FEET. ALL ROADWAY CULVERTS SHALL BE A MINIMUM 32- FOOT LENGTH.

	WETLAND IMPACT (SF)
WETLAND IMPACT #1	576
WETLAND IMPACT #2	4270
TOTAL	4846



PROJECT PARCEL TOWN OF CANDIA TAX MAP 409, LOT 228
APPLICANT/OWNER AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT QUINCY, MA 02169
TOTAL LOT AREA ± 72 ACRES

Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
REV.	DATE	REVISION	BY



Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	OVERVIEW GRADING & DRAINAGE PLAN
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
C9
SHEET 16 OF 30
JBE PROJECT NO. 24025




PROJECT PARCEL
TOWN OF CANDIA
TAX MAP 409, LOT 228

APPLICANT/OWNER
AV DEVELOPMENT, LLC
2 GRANITE RAIL COURT
QUINCY, MA 02169

TOTAL LOT AREA
± 72 ACRES

Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219
 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM



Plan Name: **GRADING AND DRAINAGE PLAN**

Project: **DIAMOND HILL SUBDIVISION
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH**

Owner of Record: **AV DEVELOPMENT, LLC
2 GRANITE RAIL COURT, QUINCY, MA 02169**


DRAWING No.
C10

SHEET 17 OF 30
JBE PROJECT NO. 24025



DRAINAGE SCHEDULE

CB 101 TYPE 'C' INLET INLET=528.00 INVOut=522.20 (P-202)	HW 001 INVin=528.50 (P-201) HW 002 INVOut=526.30 (P-201)
CB 102 RIM=526.25 INVin=516.20 (P-202) INVOut=516.10 (P-203)	FES 001 INVOut=486.00 FES 002 INVOut=476.00
P-202 60' - 25" HDPE S=0.100 FT/FT	FES 003 INVOut=518.00
P-203 189' - 24" RCP S=0.170 FT/FT	OS #1 RIM=485.00 INVOut=481.00 (P-204)
P-204 81' - 24" RCP S=0.062 FT/FT	OS #2 RIM=545.50 INVOut=539.58 (P-205)
P-205 100' - 18" RCP S=0.216 FT/FT	RIP-RAP #1 L=24.75', W1=6' W2=30.75', D50=18.75" T=46.75"
P-206 28' - 15" RCP	RIP-RAP #2 L=25.33', W1=6' W2=31.33', D50=20.33" T=50.67"
P-207 35' - 15" RCP	RIP-RAP #3 L=23', W1=6' W2=29.0', D50=15" T=37"
P-208 24' - 15" RCP	RIP-RAP #4 L=12', W1=4.5' W2=16.5', D50=3" T=7.5"
P-209 26' - 15" RCP	
P-210 22' - 15" RCP	
P-211 30' - 15" RCP	
P-212 30' - 15" RCP	
P-213 26' - 15" RCP	




PROJECT PARCEL
TOWN OF CANDIA
TAX MAP 409, LOT 228

APPLICANT/OWNER
AV DEVELOPMENT, LLC
2 GRANITE RAIL COURT
QUINCY, MA 02169

TOTAL LOT AREA
± 72 ACRES

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885

Civil Engineering Services

603-772-4746






E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	GRADING AND DRAINAGE PLAN
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169


DRAWING No.

C11

SHEET 18 OF 30
JBE PROJECT NO. 24025



Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS SHOWN	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885



Civil Engineering Services

603-772-4746


E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	PLAN AND PROFILE
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.	P1
SHEET 19 OF 30 JBE PROJECT NO. 24025	



Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		ISSUED FOR REVIEW	BY


Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219
 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM


Plan Name:	PLAN AND PROFILE
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.
P2
SHEET 20 OF 30
JBE PROJECT NO. 24025




SITE DISTANCE NOTES:



1. SIGHT DISTANCE BASED UPON TOWN OF CANDIA SUBDIVISION REGULATIONS SECTION 14.15. THE HEIGHT OF THE DRIVER'S EYE IS CONSIDERED TO BE 3.5' ABOVE THE ROAD SURFACE. THE HEIGHT OF THE OBJECT IS 30" ABOVE THE ROAD SURFACE. THE MINIMUM SIGHT DISTANCE SHALL BE ALL-SEASON SIGHT DISTANCE OF 2.5' ABOVE FINISHED GRADE.




250' SIGHT DISTANCE



150' SIGHT DISTANCE



Design: JPT Draft: KDR Date: 03/25/25
Checked: BWG Scale: AS SHOWN Project No.: 24025
Drawing Name: 24025-PLAN.dwg
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY




Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.
Civil Engineering Services

85 Portsmouth Ave. PO Box 219 Stratham, NH 03885
603-772-4746
E-MAIL: JBE@JONESANDBEACH.COM





Plan Name: **SIGHT DISTANCE PLAN**
Project: **DIAMOND HILL SUBDIVISION
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH**
Owner of Record: **AV DEVELOPMENT, LLC
2 GRANITE RAIL COURT, QUINCY, MA 02169**

DRAWING No. **P3**
SHEET 21 OF 30
JBE PROJECT NO. 24025




LOT 1

LOT 2



Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.




REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG


Designed and Produced in NH
J/B Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: **POTENTIAL DRIVEWAY PROFILES**
 Project: **DIAMOND HILL SUBDIVISION**
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
 Owner of Record: **AV DEVELOPMENT, LLC**
2 GRANITE RAIL COURT, QUINCY, MA 02169


DRAWING No. **P4**
 SHEET 22 OF 30
 JBE PROJECT NO. 24025







LOT 3




LOT 4



LOT 5



Design: JPT Draft: KDR Date: 03/25/25
Checked: BWG Scale: AS SHOWN Project No.: 24025
Drawing Name: 24025-PLAN.dwg
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG





Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Civil Engineering Services 603-772-4746
PO Box 219
Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: **POTENTIAL DRIVEWAY PROFILES**
Project: **DIAMOND HILL SUBDIVISION**
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record: **AV DEVELOPMENT, LLC**
2 GRANITE RAIL COURT, QUINCY, MA 02169




DRAWING No. **P5**
SHEET 23 OF 30
JBE PROJECT NO. 24025




LOT 6

LOT 8

LOT 9



Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.







REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY


Designed and Produced in NH
J/B Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: **POTENTIAL DRIVEWAY PROFILES**
 Project: **DIAMOND HILL SUBDIVISION**
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
 Owner of Record: **AV DEVELOPMENT, LLC**
2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No. **P6**
 SHEET 24 OF 30
 JBE PROJECT NO. 24025



Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS SHOWN Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.




REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG

Designed and Produced in NH
J/B Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name: **POTENTIAL DRIVEWAY PROFILES**
 Project: **DIAMOND HILL SUBDIVISION**
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
 Owner of Record: **AV DEVELOPMENT, LLC**
2 GRANITE RAIL COURT, QUINCY, MA 02169


DRAWING No. **P7**
 SHEET 25 OF 30
 JBE PROJECT NO. 24025



- NOTES:**
- PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL CONFORM TO STREET OPENING REGULATIONS.
 - NEW ROADWAY CONSTRUCTION SHALL CONFORM WITH PROJECT AND TOWN SPECIFICATIONS.
 - ALL BACKFILL MATERIALS ARE TO BE INSTALLED IN 12" MAXIMUM LIFTS AND COMPACTED TO 95% OF A MODIFIED PROCTOR (ASTM D-1557.)
 - PIPES SHALL BE CLASS IV OR V RCP BELL AND SPIGOT OR TONGUE AND GROOVE PIPE WITH ELASTOMERIC OIL RESISTANT COMPRESSION RING JOINTING. CLASS IV OR V SHALL BE ALLOWED UNDER SHOULDER AND GREEN AREAS, CLASS V UNDER ROADWAYS AND FILL AREAS DEEPER THAN 15-FEET.
 - PIPES SHALL HAVE A MINIMUM COVER OF 3- FEET.
 - MINIMUM CULVERT SIZE SHALL BE 15".
 - ALL ROADWAY CULVERTS SHALL BE A MINIMUM OF 32' LONG.

DRAINAGE TRENCH


NOT TO SCALE



- NOTES:**
- BASE SECTION SHALL BE MONOLITHIC WITH 48" INSIDE DIAMETER.
 - ALL SECTIONS SHALL BE DESIGNED FOR H2O LOADING.
 - CONCRETE SHALL BE COMPRESSIVE STRENGTH 4000 PSI, TYPE II PORTLAND CEMENT.
 - FRAMES AND GRATES SHALL BE HEAVY DUTY AND DESIGNED FOR H2O LOADING
 - PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2" MAX. CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL PIPE CONNECTIONS SO AS TO BE WATERTIGHT.
 - JOINT SEALANT BETWEEN PRECAST SECTIONS SHALL BE BUTYL RUBBER.
 - ALL CATCH BASIN FRAMES AND GRATES SHALL BE NHDOT CATCH BASIN TYPE ALTERNATE 1 OR NEENAH R-3570 OR APPROVED EQUAL (24"x24" TYPICAL).
 - STANDARD CATCH BASIN FRAME AND GRATE(S) SHALL BE SET IN FULL MORTAR BED. ADJUST TO GRADE WITH CLAY BRICK AND MORTAR (2 BRICK COURSES TYPICALLY, 5 BRICK COURSES MAXIMUM, BUT NO MORE THAN 12"), OR PRECAST CONCRETE 'DONUTS'.
 - ALL BACKFILL MATERIALS ARE TO BE INSTALLED IN 12" MAXIMUM LIFTS AND COMPACTED TO 95% OF A MODIFIED PROCTOR.
 - MORTAR SHALL BE TYPE 1/11 PORTLAND CEMENT.
 - ALL BACKFILL MATERIALS ARE TO BE INSTALLED IN 12" MAXIMUM LIFTS AND COMPACTED TO 95% OF A MODIFIED PROCTOR (ASTM D-1557)


CATCH BASIN

NOT TO SCALE



STOP SIGN (R1-1)

NOT TO SCALE



SECTION A-A


DIA.	HEADWALL LENGTH	HEADWALL HEIGHT	FILL HEIGHT	PIPE COVER	HEADWALL BOTTOM WIDTH
D	L	H	FH	h	W
12"	4'-2"	3'-9"	1'-6"	1'-3"	1'-11"
15"	5'-11"	4'-2"	1'-6"	1'-5"	2'-0"
18"	6'-11"	4'-5"	1'-6"	1'-5"	2'-1"
24"	8'-10"	4'-11"	1'-6"	1'-5"	2'-3"

NOTES: LONGITUDINAL SECTION

- ALL DIMENSIONS GIVEN IN FEET & INCHES.
- PROVIDE BELL END AT INLET HEADWALL, AND SPIGOT END AT OUTLET END HEADWALL.
- CONCRETE: 5,000 PSI MINIMUM AFTER 28 DAYS. CEMENT TO BE TYPE II PORTLAND CEMENT PER ASTM C-150. REINFORCING TO MEET OR EXCEED ASTM A-615 GRADE 60 DEFORMED BARS.
- 1" THREADED INSERTS PROVED FOR FINAL ATTACHMENT IN FIELD BY OTHERS.
- ALL BACKFILL MATERIALS ARE TO BE INSTALLED IN 12" MAXIMUM LIFTS AND COMPACTED TO 95% OF A MODIFIED PROCTOR (ASTM D-1557).

PRECAST CONCRETE HEADWALL


NOT TO SCALE



NOTE: ALL UTILITIES SHALL BE REVIEWED AND APPROVED BY APPROPRIATE UTILITY COMPANY.

UTILITY TRENCH

NOT TO SCALE



INTERSECTION DETAIL: DIAMOND HILL ROAD & VISTA ROAD


SCALE: 1" = 20'



- NOTES:**
- ALL STOP BARS TO BE SOLID WHITE REFLECTIVE TRAFFIC PAINT AS PER DIMENSIONS ABOVE.

STOP BAR

NOT TO SCALE




NOTES:

- ALL ROADWAY FILL SLOPES STEEPER THAN 3:1 OR GREATER THAN 5 VERTICAL FEET SHALL BE PROTECTED WITH STEEL W-BEAM GAUDDRAIL. THE GAUDDRAIL AND END-SECTIONS SHALL CONFORM TO THE MOST RECENT NHDOT REQUIREMENTS. WHERE GAUDDRAILS ARE PROPOSED, THE GRAVEL SHOULDER SHALL BE 6' WIDE. THE FACE OF THE RAIL SHALL BE PLACED OUTSIDE THE REQUIRED 5' PER FT SHOULDER. THE SHOULDER SLOPE SHALL EXTEND AT LEAST 12' BEHIND THE POSTS, PRIOR TO THE SLOPE BREAK
- REMOVE ALL ORGANICS, TOPSOIL AND MATERIAL YIELDING TO A 10 TON ROLLER. SUBBASE AREAS THAT CONTAIN UNSUITABLE MATERIALS MUST BE EXCAVATED TO A DEPTH NO LESS THAN 36" BELOW FINISH GRADE AND BE REPLACED WITH GRAVEL COMPACTED TO 95% MODIFIED PROCTOR.
- ALL MATERIALS TO BE AS SPECIFIED PER TOWN STANDARDS AND NHDOT, WHICHEVER IS MOST STRINGENT. GRADATION AND COMPACTION TEST RESULTS (95% MIN.) SHALL BE SUBMITTED FOR REVIEW AND APPROVAL.
- TOWN MAY REQUIRE UNDERDRAIN, ADDITIONAL GRAVEL AND/OR ADDITIONAL DRAINAGE IF SOIL CONDITIONS WARRANT.
- WOVEN GEOTEXTILE FABRIC SHALL BE PLACED ABOVE SUBGRADE AT ALL WETLAND CROSSINGS.
- FILL TO BE PLACED IN NOT GREATER THAN 12" LIFTS AND COMPACTED TO 95% OF THE MODIFIED PROCTOR.

TYPICAL ROADWAY SECTION

NOT TO SCALE

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS NOTED	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885

Civil Engineering Services

603-772-4746

E-MAIL: JBE@JONESANDBEACH.COM


Plan Name:	DETAIL SHEET
Project:	MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.

D1


SHEET 26 OF 30

JBE PROJECT NO. 24025




9P-GRAVEL WETLAND #1

SCALE: 1" = 40'




BIORETENTION BASIN

SCALE: 1" = 30'




INFILTRATION BASIN

NOT TO SCALE




POND STRUCTURE COVER
OUTLET STRUCTURE #1



BIOFILTRATION BASIN

NOT TO SCALE



RAIN GARDEN (GRASSED W/ UNDER DRAIN)

NOT TO SCALE

BIO-INFILTRATION MIX AND PROCEDURE:

1. REMOVE EXISTING FOREST LITTER FROM INFILTRATION BASIN SITE.
2. REMOVE SANDY LOAM AND STOCKPILE (SCREEN LARGE ROOTS).
3. REMOVE SANDY LAYERS TO 18" BELOW BASIN FLOOR ELEVATION.
4. BIO-INFILTRATION MIX: (BY VOLUME)
 - 4.1. 50%-55% ASTM C-33 CONCRETE SAND.
 - 4.2. 20%-30% LOAMY SAND TOPSOIL WITH 15%-25% FINES PASSING A #200 SIEVE
 - 4.3. 20%-30% MODERATELY FINE SHREDDED BARK OR WOOD FIBER MULCH WITH LESS THAN 5% PASSING THE #200 SIEVE.
5. INSTALL TO BIO-INFILTRATION MIX TO BASIN BOTTOM ELEVATION
6. SEED WITH "NEW ENGLAND WARM SEASON GRASS MIX" AS SOLD BY NEW ENGLAND WETLAND PLANTS, INC. OR EQUAL AS APPROVED BY ENGINEER. APPLICATION RATE = 1900 SQ.FT. / LB.
- 6.1. LIGHTLY MULCH WITH WEED FREE STRAW.

DESIGN CONSIDERATIONS

1. DO NOT DIRECT RUNOFF TO THE BIORETENTION SYSTEMS UNTIL IT HAS BEEN PLANTED AND ITS CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.
2. DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUN-OFF, WATER FROM EXCAVATIONS) TO THE BIORETENTION AREA DURING ANY STAGE OF CONSTRUCTION.
3. DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT OUTSIDE THE LIMITS OF THE INFILTRATION COMPONENTS OF THE SYSTEM.


MAINTENANCE REQUIREMENTS:

1. SYSTEMS SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND FOLLOWING ANY RAINFALL EVENT EXCEEDING 2.5 INCHES IN A 24 HOUR PERIOD, WITH MAINTENANCE OR REHABILITATION CONDUCTED AS WARRANTED BY SUCH INSPECTION.
2. PRETREATMENT MEASURES SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND CLEANED OF ACCUMULATED SEDIMENT AS WARRANTED BY INSPECTION, BUT NO LESS THAN ONCE ANNUALLY.
3. TRASH AND DEBRIS SHOULD BE REMOVED AT EACH INSPECTION.
4. AT LEAST ONCE ANNUALLY, SYSTEM SHOULD BE INSPECTED FOR DRAWDOWN TIME. IF BIORETENTION SYSTEM DOES NOT DRAIN WITHIN 72 HOURS FOLLOWING A RAINFALL EVENT, THEN A QUALIFIED PROFESSIONAL SHOULD ASSESS THE CONDITION OF THE FACILITY TO DETERMINE MEASURES REQUIRED TO RESTORE FILTRATION FUNCTION OR INFILTRATION FUNCTION (AS APPLICABLE), INCLUDING BUT NOT LIMITED TO REMOVAL OF ACCUMULATED SEDIMENTS OR RECONSTRUCTION OF THE FILTER MEDIA.
5. VEGETATION SHOULD BE INSPECTED AT LEAST ANNUALLY, AND MAINTAINED IN HEALTHY CONDITION, INCLUDING PRUNING, REMOVAL AND REPLACEMENT OF DEAD OR DISEASED VEGETATION, AND REMOVAL OF INVASIVE SPECIES.

BIORETENTION SYSTEM ELEVATIONS

ELEVATION	SYSTEM #1
A	542.00
B	540.50
C	540.25
D	539.25

Design: JPT Draft: KDR Date: 03/25/25
 Checked: BWG Scale: AS NOTED Project No.: 24025
 Drawing Name: 24025-PLAN.dwg
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.




REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY

Designed and Produced in NH
J/B Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. Civil Engineering Services 603-772-4746
 PO Box 219 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM


Plan Name: **DETAIL SHEET**
 Project: **DIAMOND HILL SUBDIVISION**
MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
 Owner of Record: **AV DEVELOPMENT, LLC**
2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No. **D2**
 SHEET 27 OF 30
 JBE PROJECT NO. 24025



DITCH TURN-OUT BASIN

SCALE: 1" = 20'




DETENTION BASIN

NOT TO SCALE

NOTES:

- CONTRACTOR SHALL PROVIDE BLOCK SUBMITTAL FOR REVIEW BY ENGINEER OF RECORD.
- IF WALL HEIGHT EXCEEDS 4- FEET, A GEOTECHNICAL OR STRUCTURAL ENGINEER MUST PREPARE AN ENGINEERED WALL DESIGN, PROVIDE FOR REVIEW PRIOR TO INSTALLATION.




TYPICAL GRAVITY WALL DETAIL

NOT TO SCALE

DETENTION POND MAINTENANCE

MAINTENANCE IS NECESSARY IF DETENTION/RETENTION BASINS ARE TO CONTINUE TO FUNCTION AS ORIGINALLY DESIGNED. A LOCAL GOVERNMENT, A DESIGNATED GROUP SUCH AS A HOME-OWNERS' ASSOCIATION OR SOME INDIVIDUAL MUST BE ASSIGNED RESPONSIBILITY FOR MAINTAINING THE STRUCTURES AND THE BASIN AREA. A MAINTENANCE PLAN SHOULD BE DEVELOPED THAT OUTLINES THE MAINTENANCE OPERATIONS AND A SCHEDULE FOR CARRYING OUT THE PROCEDURES. THE FOLLOWING ARE SOME ITEMS WHICH SHOULD BE CONSIDERED IN FORMULATING A MAINTENANCE PLAN

- EMBANKMENT --- THE EMBANKMENT SHOULD BE INSPECTED ANNUALLY TO DETERMINE IF RODENT BURROWS, WET AREAS, OR EROSION OF THE FILL IS TAKING PLACE.
- VEGETATION --- THE VEGETATED AREAS OF THE STRUCTURE SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH. LIME AND FERTILIZER SHOULD BE APPLIED AS NECESSARY AS DETERMINED BY SOIL TESTS. TREES AND SHRUBS SHOULD BE KEPT OFF THE EMBANKMENT AND EMERGENCY SPILLWAY AREAS.
- INLETS --- PIPE INLETS AND SPILLWAY STRUCTURES SHOULD BE INSPECTED ANNUALLY AND AFTER EVERY MAJOR STORM. ACCUMULATED DEBRIS AND SEDIMENT SHOULD BE REMOVED. IF PIPES ARE COATED, THE COATING SHOULD BE CHECKED AND REPAIRED AS NECESSARY.
- OUTLETS --- PIPE OUTLETS SHOULD BE INSPECTED ANNUALLY AND AFTER EVERY MAJOR STORM. THE CONDITION OF THE PIPES SHOULD BE NOTED AND REPAIRS MADE AS NECESSARY. IF EROSION IS TAKING PLACE, MEASURES SHOULD BE TAKEN TO STABILIZE AND PROTECT THE AFFECTED AREA OF THE OUTLET.
- SEDIMENT --- SEDIMENT SHOULD BE CONTINUALLY CHECKED IN THE BASIN. WHEN SEDIMENT ACCUMULATIONS REACH THE PREDETERMINED DESIGN ELEVATION, THEN SEDIMENT SHOULD BE REMOVED AND PROPERLY DISPOSED OF.
- SAFETY INSPECTIONS --- ALL PERMANENT IMPOUNDMENTS SHOULD BE INSPECTED BY A QUALIFIED PROFESSIONAL ENGINEER ON A PERIODIC BASIS. IF THERE IS POTENTIAL FOR SIGNIFICANT DAMAGE OR LOSS OF LIFE DOWNSTREAM, THEN THE INSPECTION SHOULD BE CARRIED OUT ANNUALLY. THE DESIGNATED INDIVIDUAL OR GROUP SHOULD ALSO MAKE INSPECTIONS AFTER EVERY MAJOR STORM EVENT.




NOTE:

- STABILIZED PRIOR TO DIRECTING RUN OFF TO DITCH
- CONSTRUCT GRADES SHOWN ON PROFILE

ROCK-LINED DITCH

NOT TO SCALE

STA	SIDE	RIP-RAP SIZE DSO (INCHES)	THICKNESS (INCHES)
0+00-7+00	RT.	4"	6"
7+00-13+00	RT.	6"	9"
0+00-17+60	LT.	3"	4.5"




NOTES:

- CLEANOUT FRAME SHALL BE SET IN 2' SQUARE BY 4" THICK CONCRETE COLLAR WITH 4" X 4" WELDED WIRE FABRIC AT MID-DEPTH WHEN CLEANOUT IS LOCATED IN A LANDSCAPED AREA.

UNDERDRAIN CLEANOUT DETAIL

NOT TO SCALE




NOTES:

- PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL CONFORM TO STREET OPENING REGULATIONS.
- NEW ROADWAY CONSTRUCTION SHALL CONFORM TO PROJECT AND TOWN SPECIFICATIONS.
- UNDERDRAINS SHALL BE 6 INCHES MINIMUM DIAMETER PERFORATED SDR-35 PVC INSTALLED WITH A MINIMUM OF 12 INCHES OF CRUSHED STONE AROUND THE PIPE. THE STONE SHALL BE COVERED WITH A FILTER FABRIC, WHICH HAS A WEIGHT OF 0.3 LBS/SQ. YD. AND A FLOW RATE OF 12 GPM.

ROADWAY UNDERDRAIN TRENCH

NOT TO SCALE




NOTES:

- USE IN HEAVY TRAFFIC AREAS.
- GUARD RAIL TO BE "CORE-TEN" TYPE (OR EQUIVALENT APPROVED BY THE ENGINEER).
- USE 6"-0" POSTS WHEN FILL SLOPE IS 4:1 OR FLATTER.
- ALL TIMBER POSTS TO BE TREATED WITH PRESERVATIVE MATERIAL CONFORMING TO AASHTO M133.
- POST BOLTS TO BE 18" W/MIN. 2 1/2" THREAD LENGTH.

GUARD RAIL (CORE-TEN)

NOT TO SCALE




NOTES:

- CONCRETE: 4,000 PSI @ 28 DAYS. CEMENT TO BE TYPE III PER ASTM C-150.

NHDOT CATCH BASIN TYPE "C" THROAT

NOT TO SCALE

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS NOTED	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		
THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.		



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
REV.	DATE	REVISION	BY

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885

Civil Engineering Services

603-772-4746

E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	DETAIL SHEET
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.	D3
SHEET 28 OF 30	JBE PROJECT NO. 24025

TEMPORARY EROSION CONTROL NOTES


1. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME. AT NO TIME SHALL AN AREA IN EXCESS OF 5 ACRES BE EXPOSED AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.
2. EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER.
3. ALL DISTURBED AREAS (INCLUDING POND AREAS BELOW THE PROPOSED WATERLINE) SHALL BE RETURNED TO PROPOSED GRADES AND ELEVATIONS. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 6" OF SCREENED ORGANIC LOAM AND SEEDED WITH SEED MIXTURE 'C' AT A RATE NOT LESS THAN 1.10 POUNDS OF SEED PER 1,000 S.F. OF AREA (48 LBS. / ACRE).
4. SILT FENCES AND OTHER BARRIERS SHALL BE INSPECTED EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF A RAINFALL OF 0.5" OR GREATER. ALL DAMAGED AREAS SHALL BE REPAIRED, AND SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF.
5. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VEGETATED.
6. AREAS MUST BE SEEDED AND MULCHED OR OTHERWISE PERMANENTLY STABILIZED WITHIN 3 DAYS OF FINAL GRADING, OR TEMPORARILY STABILIZED WITHIN 14 DAYS OF THE INITIAL DISTURBANCE OF SOIL. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE.
7. ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEING AND INSTALLING NORTH AMERICAN GREEN S75 EROSION CONTROL BLANKETS (OR AN EQUIVALENT APPROVED IN WRITING BY THE ENGINEER) ON SLOPES GREATER THAN 3:1, AND SEEING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.
8. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.
9. AFTER OCTOBER 15th, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3" OF CRUSHED GRAVEL PER NHDOT ITEM 304.3.
10. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:
 - a. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;
 - b. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
 - c. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH STONE OR RIPRAP HAS BEEN INSTALLED; OR
 - d. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
11. FUGITIVE DUST CONTROL IS REQUIRED TO BE CONTROLLED IN ACCORDANCE WITH ENV-A 1000, AND THE PROJECT IS TO MEET THE REQUIREMENTS AND INTENT OF RSA 430:53 AND AGR 3800 RELATIVE TO INVASIVE SPECIES.
12. PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR'S NAME, ADDRESS, AND PHONE NUMBER SHALL BE SUBMITTED TO DES VIA EMAIL (SEE BELOW).
13. PRIOR TO CONSTRUCTION, A PHASING PLAN THAT DELINEATES EACH PHASE OF THE PROJECT SHALL BE SUBMITTED. ALL TEMPORARY SEDIMENT BASINS THAT WILL BE NEEDED FOR DEWATERING WORK AREAS SHALL BE LOCATED AND IDENTIFIED ON THIS PLAN.
14. IN ORDER TO ENSURE THE STABILITY OF THE SITE AND EFFECTIVE IMPLEMENTATION OF THE SEDIMENT AND EROSION CONTROL MEASURES SPECIFIED IN THE PLANS FOR THE DURATION OF CONSTRUCTION, THE CONTRACTOR SHALL BE IN STRICT COMPLIANCE WITH THE FOLLOWING INSPECTION AND MAINTENANCE REQUIREMENTS IN ADDITION TO THOSE CALLED FOR IN THE SWPPP:
 - a. A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL OR A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NEW HAMPSHIRE ("MONITOR") SHALL BE EMPLOYED TO INSPECT THE SITE FROM THE START OF ALTERATION OF TERRAIN ACTIVITIES UNTIL THE SITE IS IN FULL COMPLIANCE WITH THE SITE SPECIFIC PERMIT ("PERMIT").
 - b. DURING THIS PERIOD, THE MONITOR SHALL INSPECT THE SUBJECT SITE AT LEAST ONCE A WEEK, AND IF POSSIBLE, DURING ANY 1/2 INCH OR GREATER RAIN EVENT (I.E. 1/2 INCH OF PRECIPITATION OR MORE WITHIN A 24 HOUR PERIOD). IF UNABLE TO BE PRESENT DURING SUCH A STORM, THE MONITOR SHALL INSPECT THE SITE WITHIN 24 HOURS OF THIS EVENT.
 - c. THE MONITOR SHALL PROVIDE TECHNICAL ASSISTANCE AND RECOMMENDATIONS TO THE CONTRACTOR ON THE APPROPRIATE BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROLS REQUIRED TO MEET THE REQUIREMENTS OF RSA 485 A:17 AND ALL APPLICABLE DES PERMIT CONDITIONS.

SEEDING SPECIFICATIONS

1. **GRADING AND SHAPING**
 - A. SLOPES SHALL NOT BE STEEPER THAN 2:1 WITHOUT APPROPRIATE EROSION CONTROL MEASURES AS SPECIFIED ON THE PLANS (3:1 SLOPES OR FLATTER ARE PREFERRED).
 - B. WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED.
2. **SEEDBED PREPARATION**
 - A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.
 - B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEING AND FUTURE MAINTENANCE OF THE AREA. WHERE FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO PREPARE A SEEDBED AND FERTILIZER AND LIME MIXED INTO THE SOIL. THE SEEDBED SHOULD BE LEFT IN A REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER PRACTICAL.
3. **ESTABLISHING A STAND**
 - A. LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF SEEING AND INCORPORATED INTO THE SOIL. TYPES AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST IS NOT AVAILABLE, THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED:
 AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100 LBS. PER 1,000 SQ.FT.
 NITROGEN(N), 50 LBS. PER ACRE OR 1.1 LBS. PER 1,000 SQ.FT.
 PHOSPHATE(P2O5), 100 LBS. PER ACRE OR 2.2 LBS. PER 1,000 SQ.FT.
 POTASH(K2O), 100 LBS. PER ACRE OR 2.2 LBS. PER 1,000 SQ.FT.
 (NOTE: THIS IS THE EQUIVALENT OF 500 LBS. PER ACRE OF 10-20-20 FERTILIZER OR 1,000 LBS. PER ACRE OF 5-10-10.)
 - B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING. WHERE BROADCASTING IS USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.
 - C. REFER TO THE 'SEEING GUIDE' AND 'SEEING RATES' TABLES ON THIS SHEET FOR APPROPRIATE SEED MIXTURES AND RATES OF SEEING. ALL LEGUMES (CROWNVETCH, BIRDSFOOT, TREFOL AND FLATPEA) MUST BE INOCULATED WITH THEIR SPECIFIC INOCULANT PRIOR TO THEIR INTRODUCTION TO THE SITE.
 - D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20th OR FROM AUGUST 10th TO SEPTEMBER 1st.
4. **MULCH**
 - A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEING.
 - B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90 LBS PER 1000 S.F.
5. **MAINTENANCE TO ESTABLISH A STAND**
 - A. PLANTED AREAS SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH.
 - B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIALS TAKE 2 TO 3 YEARS TO BECOME FULLY ESTABLISHED.
 - C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, ANNUAL MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

MAINTENANCE NOTES:

1. SEDIMENT TRAPS MUST BE INSPECTED AND MUST BE CLEANED WHEN THE ORIGINAL CAPACITY HAS BEEN REDUCED BY 50 PERCENT OR LESS, AS REQUIRED BY THE GOVERNING AGENCY.
2. ALL MATERIAL EXCAVATED FROM BEHIND SEDIMENT BARRIERS OR FROM TRAPS SHALL BE INCORPORATED INTO ON-SITE SOILS OR SPREAD OUT ON AN UPLAND PORTION OF THE SITE AND STABILIZED.
3. VERIFY THAT NO EROSION IS OCCURRING AT DISCHARGE POINTS TO AND FROM IMPOUNDMENTS AND VERIFY THAT TRAP SIDE SLOPES ARE STABILIZED AND SHOW NO SIGNS OF EROSION.
4. THE TRAP SHALL BE INSTALLED AS CLOSE TO THE DISTURBED AREA OR SOURCE OF SEDIMENT AS POSSIBLE.
5. TRAP TO BE CLEANED WHEN 50% OF ORIGINAL VOLUME IS FILLED.
6. THE MATERIALS REMOVED FROM THE TRAP SHALL BE PROPERLY DISPOSED OF AND STABILIZED.



TEMPORARY SEDIMENT TRAP

NOT TO SCALE

USE	SEEDING MIXTURE 1/	DROUGHTY	WELL DRAINED	MODERATELY WELL DRAINED	POORLY DRAINED
STEEP CUTS AND FILLS, BORROW AND DISPOSAL AREAS	A	FAIR	GOOD	GOOD	FAIR
	B	POOR	GOOD	FAIR	FAIR
	C	POOR	GOOD	EXCELLENT	GOOD
	D	FAIR	EXCELLENT	EXCELLENT	POOR
WATERWAYS, EMERGENCY SPILLWAYS, AND OTHER CHANNELS WITH FLOWING WATER.	A	GOOD	GOOD	GOOD	FAIR
	C	GOOD	EXCELLENT	EXCELLENT	FAIR
LIGHTLY USED PARKING LOTS, ODD AREAS, UNUSED LANDS, AND LOW INTENSITY USE RECREATION SITES.	A	GOOD	GOOD	GOOD	FAIR
	B	GOOD	GOOD	FAIR	FAIR
	C	GOOD	EXCELLENT	EXCELLENT	POOR
PLAY AREAS AND ATHLETIC FIELDS. (TOPSOIL IS ESSENTIAL FOR GOOD TURF.)	E	FAIR	EXCELLENT	EXCELLENT	2/
	F	FAIR	EXCELLENT	EXCELLENT	2/
GRAVEL PIT, SEE NH-PM-24 IN APPENDIX FOR RECOMMENDATION REGARDING RECLAMATION OF SAND AND GRAVEL PITS.					
1/ REFER TO SEEING MIXTURES AND RATES IN TABLE BELOW.					
2/ POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREA AND ATHLETIC FIELDS.					


NOTE: TEMPORARY SEED MIX FOR STABILIZATION OF TURF SHALL BE WINTER RYE OR OATS AT A RATE OF 2.5 LBS. PER 1000 S.F. AND SHALL BE PLACED PRIOR TO OCTOBER 15th, IF PERMANENT SEEING NOT YET COMPLETE.

SEEDING GUIDE

MIXTURE	POUNDS PER ACRE	POUNDS PER 1,000 Sq. Ft.
A. TALL FESCUE	20	0.45
CREeping RED FESCUE	20	0.45
RED TOP	2	0.05
TOTAL	42	0.95
B. TALL FESCUE	15	0.35
CREeping RED FESCUE	10	0.25
CROWN VETCH	15	0.35
OR FLAT PEA	30	0.75
TOTAL	40 OR 55	0.95 OR 1.35
C. TALL FESCUE	20	0.45
CREeping RED FESCUE	20	0.45
BIRDS FOOT TREFOL	8	0.20
TOTAL	48	1.10
D. TALL FESCUE	20	0.45
FLAT PEA	30	0.75
TOTAL	50	1.20
E. CREeping RED FESCUE 1/	50	1.15
KENTUCKY BLUEGRASS 1/	50	1.15
TOTAL	100	2.30
F. TALL FESCUE 1	150	3.60


1/ FOR HEAVY USE ATHLETIC FIELDS CONSULT THE UNIVERSITY OF NEW HAMPSHIRE COOPERATIVE EXTENSION TURF SPECIALIST FOR CURRENT VARIETIES AND SEEING RATES.

SEEDING RATES



CONSTRUCTION SPECIFICATIONS:

1. WOVEN FABRIC FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP, MID AND BOTTOM AND EMBEDDED IN THE GROUND A MINIMUM OF 8" AND THEN COVERED WITH SOIL.
2. THE FENCE POSTS SHALL BE A MINIMUM OF 48" LONG, SPACED A MAXIMUM 6' APART, AND DRIVEN A MINIMUM OF 16" INTO THE GROUND.
3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERLAPPED 6", FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY-PASSING.
4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED AND PROPERLY DISPOSED OF WHEN IT IS 6" DEEP OR VISIBLE 'BULGES' DEVELOP IN THE SILT FENCE.
5. PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE FOR SEDIMENT STORAGE.
6. SILT FENCE SHALL REMAIN IN PLACE FOR 24 MONTHS.



MAINTENANCE:


1. SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER. THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND REVEGETATED.
1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE DONE IMMEDIATELY.
2. IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.
3. SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY STORM EVENT. THE DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER.
4. SEDIMENT DEPOSITS THAT ARE REMOVED, OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED, SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

SILT FENCE

NOT TO SCALE

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS NOTED	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.




REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG
		REVISION	BY

Designed and Produced in NH
J/B Jones & Beach Engineers, Inc.
 85 Portsmouth Ave. *Civil Engineering Services* 603-772-4746
 PO Box 219
 Stratham, NH 03885 E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	EROSION AND SEDIMENT CONTROL DETAILS
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169


DRAWING No.
E1
 SHEET 29 OF 30
 JBE PROJECT NO. 24025

03/26/2025



BALED HAY OR STRAW EROSION CHECK DETAIL

NOT TO SCALE




NOTES:

1. STONE FOR STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.
2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET, 75' WITHOUT A MOUNTABLE BERM, AND EXCEPT FOR A SINGLE RESIDENTIAL LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.
3. THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES.
4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS, OR 10 FEET, WHICHEVER IS GREATER.
5. GEOTEXTILE FILTER FABRIC SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE. FILTER FABRIC IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENTIAL LOT.
6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A STONE BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.
7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO THE PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO THE PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY.

STABILIZED CONSTRUCTION ENTRANCE

NOT TO SCALE




NOTES:

1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE BLANKET.
3. ROLL THE BLANKETS (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING OPTIONAL DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" OVERLAP DEPENDING ON BLANKET TYPE. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE PREVIOUSLY INSTALLED BLANKET.
5. CONSECUTIVE BLANKETS SPICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE BLANKET WIDTH. NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.

NORTH AMERICAN GREEN
 14649 HIGHWAY 41 NORTH
 EVANSVILLE, INDIANA 47725
 1-800-772-2040

EROSION CONTROL BLANKET SLOPE INSTALLATION
 (North American Green SC150BN)

NOT TO SCALE




STONE CHECK DAM

NOT TO SCALE

MAINTENANCE NOTE:

1. STONE CHECK DAMS SHOULD BE CHECKED AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY NECESSARY REPAIRS SHOULD BE MADE IMMEDIATELY. PARTICULAR ATTENTION SHOULD BE GIVEN TO END RUN AND EROSION AT THE DOWNSTREAM TOE OF THE STRUCTURE. WHEN THE STRUCTURES ARE REMOVED, THE DISTURBED PORTION SHOULD BE BROUGHT TO THE EXISTING CHANNEL GRADE AND THE AREAS PREPARED, SEEDED AND MULCHED. WHILE THIS PRACTICE IS NOT INTENDED TO BE USED PRIMARILY FOR SEDIMENT TRAPPING, SOME SEDIMENT WILL ACCUMULATE BEHIND THE STRUCTURES. SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURES WHEN IT HAS ACCUMULATED TO ONE HALF OF THE ORIGINAL HEIGHT OF THE STRUCTURE.




NOTES:

1. TEMPORARY CULVERT INLET PROTECTION CHECK DAMS SHALL BE CONSTRUCTED OF 2"-3" STONE OVER WOVEN GEOTEXTILE FABRIC.
2. SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURE WHEN IT HAS ACCUMULATED TO ONE HALF THE ORIGINAL HEIGHT OF THE STRUCTURE.
3. SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURE WHEN IT HAS ACCUMULATED TO ONE HALF THE ORIGINAL HEIGHT OF THE STRUCTURE.
4. STRUCTURE SHALL BE REMOVED WHEN THE SITE IS STABILIZED WITH THE PROPOSED RIP RAP FIELD. AREAS OUTSIDE THE RIP RAP FIELD ARE TO BE VEGETATED AND SLOPED.

TEMPORARY CULVERT OUTLET PROTECTION CHECK DAM

NOT TO SCALE



MAINTENANCE NOTE:


1. ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAINFALL AND REPAIRS MADE AS NECESSARY. SEDIMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDIMENT HAS REACHED A MAXIMUM OF ONE HALF THE DEPTH OF THE TRAP. THE SEDIMENT SHOULD BE DISPOSED IN A SUITABLE UPLAND AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURE OR VEGETATIVE MEANS. THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE CONTRIBUTING DRAINAGE AREA TO THE INLET HAS BEEN COMPLETELY STABILIZED.

TEMPORARY CATCH BASIN INLET PROTECTION
 (Block and Gravel Drop Inlet Sediment Filter)

NOT TO SCALE

Design: JPT	Draft: KDR	Date: 03/25/25
Checked: BWG	Scale: AS NOTED	Project No.: 24025
Drawing Name: 24025-PLAN.dwg		

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM JONES & BEACH ENGINEERS, INC. (JBE). ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO JBE.



REV.	DATE	REVISION	BY
2	03/25/25	REVISED PER ENGINEER COMMENTS	BWG
1	02/20/25	REVISED PER PB COMMENTS	BWG
0	11/18/24	ISSUED FOR REVIEW	BWG

Designed and Produced in NH

J/B Jones & Beach Engineers, Inc.

85 Portsmouth Ave. Stratham, NH 03885

Civil Engineering Services

603-772-4746

E-MAIL: JBE@JONESANDBEACH.COM

Plan Name:	EROSION AND SEDIMENT CONTROL DETAILS
Project:	DIAMOND HILL SUBDIVISION MAP 409 / LOT 228: DIAMOND HILL ROAD, CANDIA, NH
Owner of Record:	AV DEVELOPMENT, LLC 2 GRANITE RAIL COURT, QUINCY, MA 02169

DRAWING No.

E2

SHEET 30 OF 30
 JBE PROJECT NO. 24025